

INLET AND MANHOLE SCHEDULE												
LOCATION		MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 F&G	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 4 F&G	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 15 F&L	INLETS, TYPE A, TYPE 3 F&G	INLETS, TYPE A, TYPE 4 F&G	INLETS, TYPE A, TYPE 8 GRATE	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	INLETS, TYPE B, TYPE 4 F&G	INLETS, TYPE B, TYPE 15 F&L	JUNCTION BOX (SPECIAL)	REMOVING INLETS
STATION		EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
HILLCREST DRIVE												
6+89.30	15.38	RT	-	-	-	1	-	-	-	-	-	-
7+03.92	23.03	RT	-	-	-	-	-	-	-	-	-	1
7+03.92	23.03	RT	-	-	1	-	-	-	-	-	-	-
7+11.10	38.59	RT	-	-	-	1	-	-	-	-	-	-
8+88.12	20.02	RT	-	-	-	-	-	-	-	-	-	1
8+88.12	20.12	RT	-	-	-	-	1	-	-	-	-	-
9+25.00	15.65	RT	-	-	-	1	-	-	-	-	-	-
9+31.46	22.39	RT	-	-	-	-	-	-	-	-	-	1
9+50.00	14.93	RT	-	-	-	-	-	-	1	-	-	-
10+06.95	23.75	RT	-	-	-	-	-	-	-	-	-	1
10+50.00	12.75	RT	-	1	-	-	-	-	-	-	-	-
10+50.00	26.58	RT	-	-	-	-	1	-	-	-	-	-
11+08.17	20.43	RT	-	-	-	-	-	-	-	-	-	1
11+10.26	14.81	RT	-	-	-	-	-	-	1	-	-	-
11+50.00	12.75	RT	-	1	-	-	-	-	-	-	-	-
12+12.50	12.75	RT	-	-	-	1	-	-	-	-	-	-
14+11.09	12.75	RT	-	-	-	1	-	-	-	-	-	-
14+11.09	22.82	RT	-	-	-	-	-	-	-	-	-	1
14+11.09	25.54	RT	-	-	-	-	1	-	-	-	-	-
14+65.97	12.75	RT	-	-	-	1	-	-	-	-	-	-
16+75.00	12.75	RT	-	-	-	1	-	-	-	-	-	-
17+75.00	12.75	RT	-	-	-	1	-	-	-	-	-	-
18+60.00	12.75	RT	-	-	-	1	-	-	-	-	-	-
18+90.11	10.76	RT	-	-	-	-	-	-	-	1	-	-
19+07.26	12.75	RT	-	1	-	-	-	-	-	-	-	-
19+35.00	12.75	RT	1	-	-	-	-	-	-	-	-	-
19+43.34	24.69	RT	-	-	-	-	-	-	-	-	-	1
19+75.00	12.75	RT	-	1	-	-	-	-	-	-	-	-
20+25.00	12.75	RT	-	1	-	-	-	-	-	-	-	-
21+25.00	12.75	RT	-	1	-	-	-	-	-	-	-	-
21+25.00	26.08	RT	-	-	-	-	1	-	-	-	-	-
22+50.00	14.81	RT	-	-	1	-	-	-	-	-	-	-
23+00.00	12.75	RT	-	-	-	-	-	-	1	-	-	-
23+49.58	24.37	RT	-	-	-	-	-	-	-	-	-	1
23+49.58	24.37	RT	-	1	-	-	-	-	-	-	-	-
23+56.54	41.72	RT	-	-	-	1	-	-	-	-	-	-
23+87.58	40.60	RT	-	-	-	1	-	-	-	-	-	-
23+94.03	23.54	RT	-	-	-	-	-	-	-	-	-	1
23+94.03	23.54	RT	-	1	-	-	-	-	-	-	-	-
SUB-TOTAL:		1	8	2	1	10	3	1	2	1	1	9
TOTAL:		1	8	2	1	10	3	1	2	1	1	9

SIGN PANEL SCHEDULE					
LOCATION		SIGN		SIGN PANEL, TYPE 1	WOOD SIGN SUPPORT
STATION				SO FT	FOOT
HILLCREST DRIVE					
23+10.00	15.00	RT	W11-2 (PEDESTRIAN)	6.25	15.5
23+10.00	15.00	RT	W16-9P (AHEAD)	2	-
25+05.00	15.00	RT	W11-2 (PEDESTRIAN)	6.25	15.5
25+05.00	15.00	RT	W16-7P (ARROW)	2	-
25+25.00	25.00	LT	W11-2 (PEDESTRIAN)	6.25	15.5
25+25.00	25.00	LT	W16-7P (ARROW)	2	-
27+75.00	19.00	LT	W11-2 (PEDESTRIAN)	6.25	15.5
27+75.00	19.00	LT	W16-9P (AHEAD)	2	-
SUB-TOTAL:				33	62
TOTAL:				33	62

ENTRANCE SCHEDULE			
LOCATION		P.C.C. DRIVEWAY PAVEMENT, 6"	DRIVEWAY PAVEMENT REMOVAL
STATION		SO YD	SQ YD
HILLCREST DRIVE			
1+11.00	RT	25	19
2+56.00	RT	22	19
3+81.00	RT	49	46
4+57.00	RT	28	25
6+58.00	RT	47	42
19+07.26	RT	52	34
SUB-TOTAL:		223	186
TOTAL:		223	186

PATCHING SCHEDULE			
LOCATION			CLASS D PATCHES, TYPE II, 8"
STATION	TO	STATION	SO YD
HILLCREST DRIVE			
11+26.10	RT	11+45.45	12
11+50.00	LT	11+50.00	12
TOTAL:			24
PAY TOTAL:			24

FENCE SCHEDULE							
LOCATION				CHAIN LINK FENCE, 4'	FENCE REMOVAL	FENCE (SPECIAL)	WOODEN FENCE REMOVAL
STATION	TO	STATION	FOOT	FOOT	FOOT	FOOT	
HILLCREST DRIVE							
8+90.85	RT	9+78.73	88	88	-	-	
12+38.62	RT	13+77.04	-	-	139	139	
SUB-TOTAL:			88	88	139	139	
TOTAL:			88	88	139	139	