

**COMBINATION CONCRETE CURB AND GUTTER REMOVAL**

LOCATION	COMBINATION CURB AND GUTTER REMOVAL (FOOT)
<b>BISSELL STREET</b>	
STA. 102+27.54 - 32.37' LT TO STA. 104+59.21 - 60.46' LT	249.9
STA. 102+32.77 TO STA. 104+13.12	373.1
STA. 102+38.08 - 31.83' RT TO STA. 105+55.75 - 50.40' RT	335.7
STA. 104+86.68 - 62.01' LT TO STA. 107+50.16 - 39.57' LT	301.4
STA. 105+33.43 - 22.40' RT TO STA. 106+18.30 - 20.28' RT	84.9
STA. 105+81.17 - 44.96' RT TO STA. 107+46.17 - 18.86' RT	180.9
STA. 107+77.95 - 43.05' LT TO STA. 111+93.94 - 45.53' LT	450.3
STA. 109+06.82 - 18.92' RT TO STA. 110+48.73 - 19.71' RT	242.3
STA. 112+28.89 - 38.80' LT TO STA. 112+47.37 - 17.60' LT	32.6
<b>KLEIN AVENUE</b>	
STA. 201+97.70 - 19.00' LT TO STA. 202+81.25 - 67.61' LT	120.4
STA. 201+97.70 - 19.00' RT TO STA. 202+83.07 - 70.01' RT	98.5
<b>TOTAL</b>	<b>2470</b>

**COMBINATION CONCRETE CURB AND GUTTER SCHEDULE**

LOCATION	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FOOT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.06 (SPECIAL) (FOOT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24 (FOOT)	CONCRETE BARRIER CURB TYPE B (FOOT)
<b>BISSELL STREET</b>				
STA. 102+27.60 - 32.00' LT TO STA. 104+59.21 - 60.46' LT	250.1			
STA. 102+31.44 TO STA. 104+06.42		360.2		
STA. 102+37.73 - 32.00' RT TO STA. 105+34.03 - 22.81' RT	297.0			
STA. 104+86.68 - 62.01' LT TO STA. 107+50.16 - 39.57' LT	302.4			
STA. 105+34.03 - 22.81' RT TO STA. 105+98.67 - 20.70' RT	64.7			
STA. 105+38.83 - 23.23' RT TO STA. 105+56.72 - 50.19' RT				34.9
STA. 105+80.19 - 45.17' RT TO STA. 105+94.27 - 21.43' RT				30.5
STA. 105+98.67 - 20.70' RT TO STA. 110+48.73 - 20.00' RT	450.1			
STA. 107+77.95 - 43.05' LT TO STA. 110+87.50 - 20.00' LT	323.5			
STA. 110+87.50 - 20.00' LT TO STA. 111+71.44 - 20.00' LT			84.4	
STA. 111+71.44 - 20.00' LT TO STA. 111+93.94 - 45.53' LT	38.6			
STA. 112+28.89 - 38.80' LT TO STA. 112+47.37 - 18.00' LT	31.1			
<b>KLEIN AVENUE</b>				
STA. 201+97.70 - 19.00' LT TO STA. 202+80.96 - 67.59' LT	117.0			
STA. 201+97.70 - 19.00' RT TO STA. 202+82.95 - 70.05' RT	99.1			
<b>TOTAL</b>	<b>1974</b>	<b>360</b>	<b>84</b>	<b>65</b>

**SIDEWALK SCHEDULE**

LOCATION	P.C.C. SIDEWALK 4" (SQ FT)
<b>BISSELL STREET</b>	
STA. 102+56.82 - 36.52' LT TO STA. 103+21.05 - 35.47' LT	240.70
STA. 103+34.96 - 37.25' LT TO STA. 104+55.95 - 83.39' LT	948.33
STA. 104+00.37 - 33.76' RT TO STA. 104+41.54 - 32.41' RT	211.55
STA. 104+65.53 - 31.63' RT TO STA. 105+48.76 - 29.41' RT	534.33
STA. 104+86.38 - 71.72' LT TO STA. 107+49.15 - 43.27' LT	1829.44
STA. 105+82.78 - 31.13' RT TO STA. 106+03.71 - 30.67' RT	101.75
STA. 107+77.82 - 46.87' LT TO STA. 108+51.94 - 26.58' LT	508.70
STA. 108+86.94 - 26.58' LT TO STA. 109+31.48 - 26.58' LT	233.40
STA. 109+66.77 - 26.58' LT TO STA. 110+37.07 - 26.58' LT	369.80
STA. 110+49.30 - 26.58' LT TO STA. 111+90.89 - 46.58' LT	890.13
STA. 112+31.20 - 29.52' LT TO STA. 112+49.36 - 28.84' LT	174.51
<b>KLEIN AVENUE</b>	
STA. 202+50.95 - 37.94' LT TO STA. 202+75.51 - 61.39' LT	238.38
STA. 202+68.37 - 45.77' RT TO STA. 202+74.20 - 73.78' RT	136.49
<b>TOTAL</b>	<b>6418</b>

**SIDEWALK REMOVAL SCHEDULE**

LOCATION	SIDEWALK REMOVAL (SQ FT)
<b>BISSELL STREET</b>	
STA. 102+54.42 - 37.22' LT TO STA. 103+23.91 - 35.91' LT	281.10
STA. 103+34.37 - 35.65' LT TO STA. 104+07.10 - 34.46' LT	294.26
STA. 104+19.26 - 34.21' LT TO STA. 104+55.95 - 83.39' LT	365.70
STA. 104+63.66 - 30.66' RT TO STA. 105+48.52 - 30.08' RT	494.81
STA. 104+86.38 - 71.72' LT TO STA. 107+49.15 - 43.27' LT	1516.43
STA. 105+83.97 - 30.84' RT TO STA. 106+03.71 - 30.67' RT	96.11
STA. 107+77.82 - 46.87' LT TO STA. 110+37.05 - 27.81' LT	1402.46
STA. 110+52.53 - 30.17' LT TO STA. 111+90.89 - 46.58' LT	754.19
STA. 112+30.87 - 28.56' LT TO STA. 112+49.36 - 28.84' LT	154.45
<b>KLEIN AVENUE</b>	
STA. 202+51.07 - 37.44' LT TO STA. 202+75.51 - 61.39' LT	252.79
STA. 202+69.18 - 48.79' RT TO STA. 202+74.20 - 73.78' RT	97.70
<b>TOTAL</b>	<b>5710</b>

**ORNAMENTAL FENCE SCHEDULE**

LOCATION	ORNAMENTAL FENCE (FOOT)
<b>BISSELL STREET</b>	
STA. 111+69.38 - 29.79' LT TO STA. 111+85.09 - 46.28' LT	22.92
STA. 111+80.95 - 82.00' LT TO STA. 111+85.09 - 46.28' LT	36.00
<b>TOTAL</b>	<b>59</b>

**DRIVEWAY SCHEDULE**

LOCATION	PCC DRIVEWAY PAVEMENT 6 INCH (SQ YD)	PCC DRIVEWAY PAVEMENT 8 INCH (SQ YD)
<b>BISSELL STREET</b>		
CE @ STA. 102+49.27 RT		18.0
PE @ STA. 102+52.18 LT	10.8	
ALLEY @ STA. 103+31.43 LT		15.3
CE @ STA. 103+85.63 RT		60.0
CE @ STA. 104+51.69 RT		31.4
CE @ STA. 108+69.44 LT		27.3
CE @ STA. 109+52.57 LT		55.5
ALLEY @ STA. 110+46.76 LT		21.6
<b>TOTAL</b>	<b>11</b>	<b>229</b>

**SIGN SCHEDULE**

LOCATION	LT/RT	PROPOSED OFFSET (FOOT)	DESCRIPTION	SIGN PANEL TYPE 1 (SQ FT)	METAL POST SIGN ASSEMBLY	
					TYPE A (FOOT)	TYPE B (FOOT)
<b>BISSELL STREET</b>						
STA. 104+77.35	RT	34.07	W4-2R (30"X30")	6.25	2 @ 14.0	
STA. 105+83.92	RT	35.77	R1-1 (30"X30")	6.25		1 @ 13.5
STA. 110+84.42	LT	28.97	R1-5L (30"X30")	6.25		1 @ 13.5
<b>KLEIN AVENUE</b>						
STA. 202+60.44	RT	43.16	R1-1 (30"X30")	6.25		1 @ 13.5
<b>TOTAL</b>				<b>25</b>	<b>28</b>	<b>41</b>

**DETECTABLE WARNINGS SCHEDULE**

LOCATION	DETECTABLE WARNINGS (SQ FT)
<b>BISSELL STREET</b>	
STA. 104+47.18 - 37.59' LT TO STA. 104+52.87 - 40.70' LT	12.4
STA. 104+93.47 - 38.33' LT TO STA. 104+98.80 - 35.03' LT	11.9
STA. 105+34.05 - 23.39' RT TO STA. 105+48.28 - 28.93' RT	27.8
STA. 105+87.39 - 30.64' RT TO STA. 105+89.39 - 30.64' RT	10.0
STA. 107+43.46 - 23.27' LT TO STA. 107+45.74 - 28.15' LT	10.0
STA. 107+82.76 - 27.58' LT TO STA. 107+88.62 - 22.58' LT	12.0
STA. 110+74.41 - 20.58' LT TO STA. 110+80.46 - 22.58' LT	12.0
STA. 111+81.77 - 29.34' LT TO STA. 111+83.70 - 24.32' LT	10.0
STA. 112+34.82 - 23.91' LT TO STA. 112+36.86 - 28.90' LT	10.0
<b>KLEIN AVENUE</b>	
STA. 202+66.39 - 38.14' LT TO STA. 202+71.83 - 41.34' LT	12.0
STA. 202+68.96 - 46.41' RT TO STA. 202+74.09 - 56.58' RT	16.9
<b>TOTAL</b>	<b>145</b>