

SEEDING SCHEDULE

LOCATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING CLASS 1	NITROGEN FERT NUTR	PHOSPHORUS FERT NUTR	POTASSIUM FERT NUTR	MULCH METHOD 2
	(LB)	(ACRE)	(LB)	(LB)	(LB)	(ACRE)
BISSELL STREET						
STA. 102+27.50 TO STA. 112+51.17	20	0.2	18	18	18	0.2
TOTAL	20	0.2	18	18	18	0.2

CHAIN LINK FENCE REMOVAL SCHEDULE

LOCATION	CHAIN LINK FENCE REMOVAL (FOOT)
BISSELL STREET	
STA. 108+51.94 - 30.09' LT TO STA. 108+86.94 - 30.37' LT	35.00
STA. 109+30.94 - 30.73' LT TO STA. 109+42.86 - 30.83' LT	11.93
STA. 110+53.78 - 33.35' LT TO STA. 111+86.94 - 29.58' LT	133.73
STA. 111+80.95 - 82.00' LT TO STA. 111+86.94 - 29.58' LT	52.77
TOTAL	233

INLET AND PIPE PROTECTION SCHEDULE

LOCATION	DISTANCE (FOOT)	INLET AND PIPE PROTECTION (EACH)
BISSELL STREET		
STA. 102+76.83 LT	30.83	1
STA. 103+66.47 LT	29.37	1
STA. 103+66.69 LT	42.73	1
STA. 103+99.33 LT	39.00	1
STA. 104+00.67 LT	28.81	1
STA. 104+32.17 LT	38.20	1
STA. 104+48.33 LT	33.46	1
STA. 104+99.76 LT	29.47	1
STA. 105+52.51 RT	20.69	1
STA. 107+34.13 LT	21.68	1
STA. 107+50.89 LT	30.44	1
STA. 107+79.76 LT	30.30	1
STA. 107+97.70 LT	19.35	1
STA. 108+38.94 LT	22.00	1
STA. 108+38.94 RT	19.72	1
STA. 109+63.73 RT	23.26	1
STA. 110+20.00 RT	19.72	1
STA. 110+20.00 LT	22.00	1
STA. 110+44.95 LT	19.00	1
STA. 110+82.53 RT	45.22	1
STA. 111+49.08 RT	48.92	1
STA. 111+92.39 LT	33.50	1
STA. 112+29.24 LT	30.42	1
TOTAL		23

PERIMETER EROSION BARRIER SCHEDULE

LOCATION	PERIMETER EROSION BARRIER (FOOT)
BISSELL STREET	
STA. 102+55.28 - 37.96' LT TO STA. 102+78.60 - 37.58' LT	23.3
STA. 102+78.27 - 40.58' LT TO STA. 103+01.50 - 40.20' LT	23.2
STA. 103+05.29 - 40.14' LT TO STA. 103+22.76 - 39.86' LT	17.5
STA. 103+34.69 - 41.28' LT TO STA. 103+43.30 - 43.29' LT	8.8
STA. 103+49.39 - 44.86' LT TO STA. 103+86.99 - 41.11' LT	38.5
STA. 103+91.78 - 41.14' LT TO STA. 104+06.72 - 41.15' LT	15.0
STA. 104+20.18 - 41.00' LT TO STA. 104+51.79 - 55.48' LT	39.1
TOTAL	165

CORRUGATED MEDIAN REMOVAL

LOCATION	CORRUGATED MEDIAN REMOVAL (SQ FT)
BISSELL STREET	
STA. 103+88.35 TO STA. 105+02.94	458.0
TOTAL	458

PAVEMENT REMOVAL SCHEDULE

LOCATION	PAVEMENT REMOVAL (SQ YD)
BISSELL STREET	
STA. 102+31.48 TO STA. 111+71.44	4960.1
TOTAL	4960

MEDIAN REMOVAL SCHEDULE

LOCATION	MEDIAN REMOVAL (SQ FT)
BISSELL STREET	
STA. 102+32.77 TO STA. 104+10.84	1244.0
TOTAL	1244

GATES REMOVAL SCHEDULE

EXISTING LOCATION	GATES REMOVAL (EACH)
BISSELL STREET	
STA. 109+42.86 - 30.83' LT TO STA. 109+69.31 - 31.23' LT	1
TOTAL	1

CONCRETE STEP REMOVAL SCHEDULE

LOCATION	CONCRETE STEP REMOVAL (EACH)
BISSELL STREET	
STA. 103+01.24 - 42.90' LT TO STA. 103+04.77 - 43.46' LT	1
STA. 103+44.09 - 39.35' LT TO STA. 103+48.15 - 39.72' LT	1
STA. 103+60.42 - 38.26' LT TO STA. 103+64.17 - 38.10' LT	1
STA. 103+87.31 - 40.10' LT TO STA. 103+91.31 - 40.04' LT	1
TOTAL	4