

THOUVENOT, WADE & MOERCHEN, INC.
ENGINEERS • SURVEYORS • PLANNERS



* COST INCLUDED IN EARTH EXCAVATION
NO ADDITIONAL COMPENSATION WILL
BE PROVIDED.

CORPORATE OFFICE
4940 OLD COLLINGSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
corp@twm-inc.com

WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
waterloo@twm-inc.com

EDWARDSVILLE OFFICE
10158 CENTURY DRIVE
EDWARDSVILLE, ILLINOIS 62025
TEL (618) 656-4040
FAX (618) 656-4343
edwardsville@twm-inc.com

ST. LOUIS OFFICE
1001 CRAIG ROAD, SUITE 260
ST. LOUIS, MISSOURI 63146
TEL (314) 236-8052
FAX (314) 872-2194
stlouis@twm-inc.com

PROFESSIONAL REGISTRATIONS LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM 184-011210
ILLINOIS PROFESSIONAL ENGINEERING CORP. 02-003370
ILLINOIS PROFESSIONAL STRUCTURAL ENGINEER CORP. 01-002022
ILLINOIS PROF. LAND SURVEYING CORP. 048-000029
MISSOURI PROFESSIONAL ENGR. CORP. MC 001528
MISSOURI LAND SURVEYING CORP. MC 000316

SEAL

Signature: _____
Signature Date: _____
Expiration Date: _____
STATEMENT OF RESPONSIBILITY
I hereby certify that the document herein to be authorized by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be used for any other part of the architectural, engineering or survey project.

TITLE: **SHILOH STATION ROAD PHASE 3
SCHEDULE OF QUANTITIES
12-0001-03-PV**
PROJECT: **SHILOH STATION ROAD
RECONSTRUCTION - PHASE 3
VILLAGE OF SHILOH
ST. CLAIR COUNTY, ILLINOIS**

REV	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY: NTS SHEET
DESIGNED BY: NTS **4**
CHECKED BY: OF 23 SHEETS
APPROVED BY: PROJECT DESCRIPTION
PROJECT NUMBER: T01100602
 ISSUED FOR REVIEW ISSUED FOR BIDDING
 ISSUED FOR CONSTR. RECORD DRAWING

REMOVAL SCHEDULE

FROM LOCATION STATION, DIRECTION	TO LOCATION STATION, DIRECTION	TREE REMOVAL (ACRE)	PAVEMENT REMOVAL (SQ YD)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	PIPE CULVERT REMOVAL (FOOT)	REMOVE EXISTING RIPRAP (SQ YD)	CONCRETE WALL REMOVAL *(FOOT)	RAILROAD TIE REMOVAL *(FOOT)
35+50.00	43+75.00		1982.0					
35+50.00 LT	43+75.00 LT							
35+50.00 RT	43+75.00 RT							
35+92.25 LT	38+83.00 LT	0.15						
36+24.05 LT	38+54.90 LT					105.0		
38+57.36 LT	38+98.12 LT				44.3			
39+00.51 LT	39+13.84 LT					9.1		
40+71.87 RT	41+05.35 RT			63.0				
40+72.23 RT	41+06.36 RT				34.1			
40+72.58 RT	-						5.9	
41+06.07 RT	-						7.0	
42+37.64 LT	42+77.32 LT	0.01						
42+90.84 RT	43+14.95 RT				24.1			
42+91.34 RT	-							7.6
42+91.85 RT	43+13.76 RT			39.3				
43+14.60 RT	-							7.9
TOTAL		0.25	1982	102	103	114	12.9	15.5

PAVING AND SIDEWALK SCHEDULE

FROM LOCATION STATION, DIRECTION	TO LOCATION STATION, DIRECTION	PROCESING MODIFIED SOILS (SQ YD)	LIME (TON)	AGGREGATE BASE COURSE TYPE B - 4" (SQ YD)	HOT - MIX ASPHALT BINDER COURSE 1L - 19.0, N 70 (TON)	HOT - MIX ASPHALT SURFACE COURSE MIX "C", N 70 (TON)	PORTLAND CEMENT CONCRETE SIDEWALK - 4" (SQ FT)	DETECTABLE WARNINGS (SQ FT)	COMBINATION CONCRETE CURB & GUTTER TYPE B - 6.18 (FOOT)	CLASS SI CONCRETE OUTLET (CU YD)	AGGREGATE SHOULDERS TYPE B - 10" (SQ YD)
35+50.00	43+75.00	3178.6	61.2								
35+50.00 LT	36+00.00 LT										10.9
35+50.00 RT	36+00.00 RT										11.7
36+00.00	43+25.00				1115.6	262.5					
36+00.00 LT	43+25.00 LT								732.5		
36+00.00 RT	43+25.00 RT								717.5		
36+00.00 LT	38+51.07 LT			143.2			1288.4				
36+00.00 RT	40+73.71 RT			410.9			3697.8				
38+37.17 LT	38+73.29LT								79.3		
38+51.07 LT	-							12			
38+73.29LT	-									3.0	
38+95.70 LT	-									3.0	
38+87.93 LT	38+95.70 LT								68.4		
38+95.37 LT	-							12			
38+97.37 LT	43+25.00 LT			242.8			2185				
41+06.22 RT	42+91.77 RT			164.9			1484.4				
43+13.87 RT	43+25.00 RT			4.6			41.6				
43+25.00 LT	43+75.00 LT										9.9
43+25.00 RT	43+75.00 RT										10.6
TOTAL		3179	61	966	1116	263	8697	24	1598	6.0	43