



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2014

SUBJECT: FAS 929 (CH 1)
Section 10-00087-00-BR
Massac County
Contract No. 99518
Item 100
April 25, 2014 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

- 1. Revised the Table of Contents to the Special Provisions.**
- 2. Revised page 3 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with the initials "P.E." written in a smaller font to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

TABLE OF CONTENTS

<u>ITEM</u>	<u>PAGE</u>
REFERENCES	1
DESCRIPTION OF WORK	1
TRAFFIC CONTROL	1
UTILITIES.....	1
CHANNEL EXCAVATION	2
GUARDRAIL REMOVAL	2
REMOVAL OF EXISTING STRUCTURES.....	2
PIPE CULVERT REMOVAL	2
SEEDING, CLASS 2 (SPECIAL)	2
STONE DUMPED RIPRAP.....	3
POWER LINES	3
TRAFFIC CONTROL MAP.....	4-5
"404" PERMIT.....	6-7
SOIL BORINGS	8-11

The above work will be paid for at the contract unit price per acre for Seeding, Class 2 (Special) which shall be payment in full for all materials, labor, equipment and any other items necessary to complete the work as specified above.

STONE DUMPED RIPRAP

This work shall be performed in accordance with Section 281 of the Standard Specifications except as modified herein.

Article 281.04 Delete the requirement for filter fabric and no bedding stone will be required.

This work will be paid for at the contract unit price per ton for STONE DUMPED RIPRAP of the class specified. Excavation required for installation will not be paid for separately but shall be included in the cost of the riprap.

POWER LINES

The Contractor shall be aware of the overhead power lines that cross the roadway approximately 27 feet above the location of the proposed north abutment. Relocation or removal of the power line is not possible. The power lines can be de-energized during the daytime periods to allow for driving piling and setting of the deck beams. De-energizing the power lines during the overnight period will not be allowed. The Contractor will be required to adjust his method of construction for the restrictions imposed by the power lines and to coordinate his work with the power company in order to minimize the periods when the power lines need to be de-energized.

The Contractor will be required to follow all clearance requirements established by the power company, OSHA, IDOT or any other pertinent governing body that has jurisdiction over this power line and/or project. All material, equipment and labor, including special construction techniques, for accomplishing any work affected by the power lines shall be included in the contract unit prices for the various items in the contract and no additional compensation will be allowed.