

SUMMARY OF QUANTITIES				
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150520	MOBILIZATION	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR152480	SHOULDER ADJUSTMENT	S.Y.	600	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	15,200	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	4,560	
AR754210	CONCRETE CURB	L.F.	545	
AR754900	REMOVE CONCRETE CURB	L.F.	453	
AR754924	REPLACE COMB CURB & GUTTER	L.F.	29	
AR800419	MODIFY TRAFFIC ISLAND	L.S.	1	
AR800433	TEMPORARY PAVEMENT	L.S.	1	
AR800441	ULTRA-THIN WHITE TOPPING 3"-CONCRETE WITH FIBERS, DELIVERED	C.Y.	1,538	
AR800442	ULTRA-THIN WHITE TOPPING 3"-CONCRETE PLACEMENT	S.Y.	15,205	
AR800571	PAVEMENT MARKING - SPECIAL, HANDICAP SYMBOL	EA.	8	
AR800572	PAVEMENT MARKING - SPECIAL, ARROW - STRAIGHT	EA.	29	
AR910230	HANDICAP SIGN	EA.	8	

INDEX TO SHEETS	
SHEET NUMBER	SHEET TITLE
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROJECT LAYOUT
4	PROPOSED SAFETY AND PHASING PLAN
5	PROPOSED PAVEMENT PREPARATION PLAN
6	TYPICAL SECTIONS AND DETAILS
7	PROPOSED CONSTRUCTION PLAN
8	PROPOSED JOINTING PLAN
9	PROPOSED JOINTING PLAN
10	PROPOSED MARKING PLAN
11	PROPOSED MARKING DETAILS

MAR 14, 2014 3:02 PM ST0LZ01547  
 pw:\SPL-SR0306.hanson.dom\hanson Projects\Documents\13jobs\1340013D\CAD\Airport\Browet\c04025-F2P-34E

REVISION	DATE



**DECATUR, ILLINOIS**  
 IL PROJ.: DEC-4271

Hanson Proj. No. 13A0013	Drawn	JRH	03/07/14
Filename C-002-FLP.dwg	Reviewed	BSS	03/14/14
Scale NOT TO SCALE	LAYOUT	JRH	03/07/14
Date 02/28/14	DRAWN	JRH	03/07/14
	REVIEWED	BSS	03/14/14



**HANSON**  
 © Copyright Hanson Professional Services Inc. 2014  
**Hanson Professional Services Inc.**  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2886  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REHABILITATE TERMINAL  
 AUTO PARKING LOT

SUMMARY OF QUANTITIES  
 AND INDEX TO SHEETS