



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 8, 2025

SUBJECT IL 53 (W. Frontage Rd)  
Section 2023-928-RS,SW  
Cook County  
Contract 62W50

Item No. 41, April 25<sup>th</sup>, 2025 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages i-ii of the Table of Contents of the Special Provisions.
2. Revised page 21 of the Special Provisions.
3. Revised sheets 9-11 of the plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

## TABLE OF CONTENTS

LOCATION OF IMPROVEMENT .....	1
DESCRIPTION OF IMPROVEMENT .....	1
MAINTENANCE OF ROADWAYS (D1) .....	2
STATUS OF UTILITIES (D-1) .....	2
CONSTRUCTION LAYOUT SPECIAL FOR RESURFACING WITH ADA AND STAND ALONE ADA (D1) .	4
PUBLIC CONVENIENCE AND SAFETY (D1) .....	6
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1) .....	6
CLEANING EXISTING DRAINAGE STRUCTURES (D1) .....	12
ADJUSTMENTS AND RECONSTRUCTIONS (D1).....	12
CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D1).....	13
ENGINEER'S FIELD OFFICE TYPE A (D1) .....	14
TRAFFIC CONTROL PLAN (D1) .....	15
FRICTION AGGREGATE (D1).....	15
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1) .....	18
TEMPORARY INFORMATION SIGNING .....	19
GRADING AND SHAPING SHOULDERS (D1) .....	20
DRIVEWAY REMOVAL AND REPLACEMENT.....	20
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC) .....	21
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE) .....	22
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	23
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES; CONCRETE, AND MORTAR (BDE) .....	24
COMPENSABLE DELAY COSTS (BDE) .....	33
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) .....	37
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....	38
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	41
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE).....	42
PAVEMENT MARKING INSPECTION (BDE) .....	42
PERFORMANCE GRADED ASPHALT BINDER (BDE) .....	43
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	48
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	49
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) .....	53
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	53
SUBMISSION OF BIDDERS LIST INFORMATION (BDE) .....	54
SUBMISSION OF PAYROLL RECORDS (BDE).....	54
SURVEYING SERVICES (BDE) .....	55

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	55
WEEKLY DBE TRUCKING REPORTS (BDE).....	55
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) .....	56
WORKING DAYS (BDE) .....	57

A ½-inch thick expansion joint shall be provided at the junction of the PCC driveway apron and curb, and at the junction of the PCC driveway apron and sidewalk.

Replacement of existing HMA driveway shall be constructed to match the thickness of the existing pavement removed; however, the minimum thickness and HMA items shall be as shown on District 1 BD-01/02 "Driveway Details" detail.

Replacement of existing PCC driveway shall be in accordance with Section 423 of the Standard Specifications. It shall be constructed to match the thickness of the existing pavement removed; however, the minimum thickness shall be as shown on District 1 BD-01/02 "Driveway Details" detail.

Method of Measurement. This work will be measured for payment in place and the area computed in square yards.

Basis of Payment. This work will be paid for at the contract unit price per SQUARE YARD for DRIVEWAY SURFACE REMOVAL AND REPLACEMENT, of the thickness specified.

#### **REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)**

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

The following contract specific work areas shall be monitored by the environmental firm for soil contamination and workers protection.

**Intersection of Wilke Road and Victoria Drive, Palatine, Cook County.** All excavation planned at the northwest quadrant, northwest island, southwest island, and southwest quadrant at the intersection of Wilke Road and Victoria Drive. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

**Intersection of Wilke Road and Lake Louise Condominium Entrance Drive (north entrance), Palatine, Cook County.** All excavation planned at the northwest quadrant, and southwest quadrant at the intersection of Wilke Road and Lake Louise Condominium Entrance Drive (north entrance). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

**Intersection of Wilke Road and Lake Louise Condominium Entrance Drive (south entrance), Palatine, Cook County.** All excavation planned at the northwest quadrant, and southwest quadrant at the intersection of Wilke Road and Lake Louise Condominium Entrance Drive (south entrance). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

**Intersection of Wilke Road and Anderson Drive, Palatine, Cook County.** All excavation planned at the southeast quadrant at the intersection of Wilke Road and Anderson Drive. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Work Zones. Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: None

1