

MODEL: Default
FILE: \\MPC-PRJ\usd-aw-bentley.com\PROJECTS\DOT OFFICES\District 4\Projects\DA 68A65\CADD\DWG\CAD\sheet1D168A65-shc-500.dgn

					CONSTRUCTION CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY		TAZEWELL COUNTY 80% FED/20% STATE	TAZEWELL COUNTY 80% FED/20% STATE	TAZEWELL COUNTY 80/10/10	TAZEWELL COUNTY 80% FED/20% STATE
					ROADWAY	BOX CULVERT	TRAFFIC SIGNALS	NONE
					0004	0004	0021	0044
					RURAL	S.N. 090-2507	RURAL	RURAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	38		38			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	257		257			
20100500	TREE REMOVAL, ACRES	ACRE	0.5		0.5			
*	20101400	NITROGEN FERTILIZER NUTRIENT	POUND	600	600			
*	20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	600	600			
*	20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	600	600			
20200100	EARTH EXCAVATION	CU YD	8040		8040			
20400800	FURNISHED EXCAVATION	CU YD	1730		1730			
20700220	POROUS GRANULAR EMBANKMENT	CU YD	148			148		
20800150	TRENCH BACKFILL	CU YD	645		645			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	143			143		
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	14475	14475			
*	25000100	SEEDING, CLASS 1	ACRE	5.25	5.25			
*	25000300	SEEDING, CLASS 3	ACRE	1	1			

*= SPECIALTY ITEM

	USER NAME = \$USERS	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					693	118R5-8,W-2	TAZEWELL	292	11
	PLOT SCALE = 1:100	CHECKED -	REVISED +					CONTRACT NO. 68A65				
	PLOT DATE = 2/14/2025	DATE -	REVISED +		SCALE:	SHEET 1	OF 17 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

MODEL: Default
FILE: \\miller-pw-bentley.com\p\m\DOT\Documents\DOT_Offices\Dirctr_4\Projects\DA_68A65\CADD\DWG\CADD\sheet\168A65-shc-schedule.dgn

LOCATION				INFORMATION ONLY						
				EARTH EXCAVATION	FURNISHED EXCAVATION	EARTH EXCAVATION ADJUST FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE 4"	
										CU YD
IL 9										
RT										
STA.	367+50.0	TO	412+50.0	3091.0	2106.0	1734.0	3840.0	-2106.0		5445.1
STA.	412+50.0	TO	435+00.0	710.0	-375.2	375.2	0.0	375.2		1268.4
LT										
STA.	367+50.0	TO	412+50.0	3749.0		2178.9	1591.0	587.9		6394.8
STA.	412+50.0	TO	435+00.0	488.0		343.9	26.0	317.9		1366.0
SUBTOTAL				8038.0	1730.8	4632.0	5457.0	-825.0		14474.3
TOTAL				8040.0	1730.0					14475.0
Cut and Fills were calculated assuming 4" vegetation removal										
Non-Special Waste areas were not included in calculation for Furnished Ex.										

REGULATED SUBSTANCES SCHEDULE					
LOCATION	NON-SPECIAL WASTE DISPOSAL	REGULATED SUBSTANCES PRE- CONSTRUCTION PLAN	REGULATED SUBSTANCES MONITORING	REULATED SUBSTANCES FINAL CONSTRUCTION REPORT	SOIL DISPOSAL ANALYSIS
	CU YD	LSUM	CAL DAY	LSUM	EACH
IL 9					
JOBSITE	285.0	1.0	17.0	1.0	3.0
SUBTOTAL	285.0	1.0	17.0	1.0	3.0
TOTAL	285.0	1.0	17.0	1.0	3.0
SEE SPECIAL PROVISIONS FOR LOCATIONS					

BUILDING REMOVAL SCHEDULE			
LOCATION	BUILDING REMOVAL NO. 1	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1
	LSUM	LSUM	LSUM
IL 9			
504 W. PEARL ST.	1.0	1.0	1.0
TOTAL	1.0	1.0	1.0

PAVEMENT PATCHING SCHEDULE							
LOCATION	CLASS D PATCHES, TYPE I, 15 INCH	CLASS D PATCHES, TYPE II, 15 INCH		CLASS D PATCHES, TYPE III, 15 INCH		CLASS D PATCHES, TYPE IV, 15 INCH	
	SQ. YD.	#	SQ. YD.	#	SQ. YD.	#	SQ. YD.
EASTBOUND							
WEST END OF PROJECT							
		0	0.0	0	0.0	4	226.7
WEST ST.							
		5	42.7	0	0.0	0	0.0
SAMPSON ST.							
JAMES ST.							
		3	29.3	0	0.0	1	100.0
HARRIS ST.							
		6	58.7	1	16.0	1	26.7
CHESTNUT ST.							
		1	8.0	1	20.0	0	0.0
EAST END OF PROJECT							
EAST BOUND TOTAL		15	139	2	36	6	353
WESTBOUND							
EAST END OF PROJECT							
CHESTNUT ST.							
		0	0.0	0	0.0	2	53.3
HARRIS ST.							
		3	30.7	0	0.0	1	26.7
JAMES ST.							
SAMPSON ST.							
		2	16.0	0	0.0	0	0.0
LOCUST ST.							
WEST ST.							
		5	42.7	2	40.0	5	380.0
OLD IL 9							
		2	13.3	0	0.0	10	620.0
END OF PROJECT							
WESTBOUND TOTAL		12	103	2	40	18	1080
SUBTOTAL		27.0	241.3	4.0	76.0	24.0	1433.3
SUBTOTAL FROM STORM SEWER SCHEDULE	5.5		19.9		84.9		62.7
WINTER BREAKUP (15%)			36.2		11.4		215.0
PROJECT TOTAL	6.0		297.0		172.0		1711.0

TREE REMOVAL SCHEDULE				
LOCATION	OFFSET	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE REMOVAL (ACRES)
		UNIT	UNIT	ACRE
IL 9				
STA. 398+33	86 FT. RIGHT		42.0	
	46 FT. RIGHT		42.0	
STA. 399+12	45 FT. RIGHT		36.0	
STA. 400+59	46 FT. RIGHT		36.0	
LT. STA. 398+00 TO 405+00				0.46
STA. 409+57	54 FT. LEFT		36.0	
STA. 412+30.0	75 FT. LEFT		65.0	
STA. 415+68	32 FT. RIGHT	15.0		
STA. 416+04	32 FT. RIGHT	15.0		
STA. 417+90	45 FT. RIGHT	8.0		
SUBTOTAL		38.0	257.0	0.5
TOTAL		38.0	257.0	0.5

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	USER NAME = \$USERS		DESIGNED -	REVISED -	SCHEDULES OF QUANTITIES	SCALE:	SHEET 1 OF 14 SHEETS	STA.	TO STA.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN -		CHECKED -	REVISED -						693	118R5-8,W-2	TAZEWELL	292	28
	PLOT SCALE = 1:100		CHECKED -	REVISED -						CONTRACT NO. 68A65				
	PLOT DATE = 3/14/2025		DATE -	REVISED -						ILLINOIS FED. AID PROJECT				