

SUMMARY OF QUANTITIES				CONSTRUCTION CODE		
				0044	0044	0028
				100% FEDERAL	100% FEDERAL	100% FEDERAL
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ELEMENT 1	ELEMENT 2	ELEMENT 3
44004250	PAVED SHOULDER REMOVAL	SQ YD	35	35		
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	37	37		
50105220	PIPE CULVERT REMOVAL	FOOT	488	10	388	90
50200100	STRUCTURE EXCAVATION	CU YD	151	85	66	
50300225	CONCRETE STRUCTURES	CU YD	12.3		12.3	
50300280	CONCRETE ENCASEMENT	CU YD	6.5		6.5	
50800105	REINFORCEMENT BARS	POUND	1,850		1,850	
51201800	FURNISHING STEEL PILES HP14X73	FOOT	144		144	
51202305	DRIVING PILES	FOOT	124		124	
51602000	PERMANENT CASING	FOOT	56		56	
52100510	ANCHOR BOLTS, 3/4"	EACH	16		16	
54010603	PRECAST CONCRETE BOX CULVERTS 6' X 3'	FOOT	30		30	
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	320	22	156	142
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	72		72	

14