

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4523	4523					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2193	2193					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	16848	16848					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	940	940					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	50 FT	495	495					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1705	1705					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46735	46735					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1535	1535					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4523	4523					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2373	2373					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2193	2193					* B2001616	TREE, CRATAEGUS CRUSCALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	18	18					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	940	940					* B2006126	TREE, SYRINGA PEKINENSIS ZHING ZHIMING (BEIJING GOLD PEKING LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	22	22					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	50 FT	1872	1872					* K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	5	5					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	50 FT	495	495					X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	50 YD	227	227					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46735	46735														

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				CHICAGO RD. SUMMARY OF QUANTITIES				F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN	REVISED									2921	(S,B&R) RS-8	COOK	34	4	
		CHECKED	REVISED									CONTRACT NO. 60B56					
		DATE	REVISED									FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					
PLOT SCALE + 1/8" = 100.0000'		PLOT DATE + 1/8/2013		SCALE:		SHEET NO. OF SHEETS		STA. TO STA.									