

SUMMARY OF QUANTITIES		UNIT	TOTAL	CONSTRUCTION CODE				
CODE NO.	ITEM DESCRIPTION			0003	0010	0021	0031	0040
				RDWY	BRIDGE	SIGNALS LIGHTING	LNDSCP	RET. WALL
31200502	STABILIZED SUBBASE HOT-MIX ASPHALT, 4 1/2"	SQ YD	4,081	4,081				
35300410	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2"	SQ YD	4,010	4,010				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	174	174				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,308	9,308				
40600300	AGGREGATE (PRIME COAT)	TON	178	178				
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	134	134				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,840	1,840				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	229	229				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	252	252				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4,942	4,942				
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	14,586	14,586				

URBAN  
901-FED  
101-STATE

• SPECIALTY ITEM

**PATRICK ENGINEERING**  
PATRICK ENGINEERING INC  
4970 VARSITY DRIVE  
LISLE, IL 60532  
patrickengineering.com

USER NAME = tkoeppen(Rdwy.Lisls)  
PLOT CONFIG = PDF(Grey\_Small).plt  
PLOT SCALE = 1:1000  
PLOT DATE = 2/18/2013 4:37:13 PM

DESIGNED - CPK  
DRAWN - MJP  
CHECKED - JAH  
DATE - 2/18/2013

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET S00-03 OF 36 STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2746	1616B	COOK	404	6
			60J14	