


SUMMARY OF QUANTITIES		UNIT	URBAN 90% FED. 10% STATE TOTAL	CONSTRUCTION CODE				
CODE NO.	ITEM DESCRIPTION			0003 RDWY	0010 BRIDGE	0021 SIGNALS LIGHTING	0031 LNDSCP	0040 RET. WALL
50300300	PROTECTIVE COAT	SQ YD	5,641		5,369			272
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1			
50500505	STUD SHEAR CONNECTORS	EACH	22,500		22,500			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	657,380		610,570			46,810
50800515	BAR SPLICERS	EACH	2,834		2,834			
50800530	MECHANICAL SPLICERS	EACH	504		504			
50901730	BRIDGE FENCE RAILING	FOOT	645		645			
51100100	SLOPE WALL, 4"	SQ YD	562		562			
51201600	FURNISHING STEEL PILES, HP 12X53	FOOT	7,308		7,308			
51202305	DRIVING PILES	FOOT	7,308		7,308			
51203600	TEST PILE STEEL, HP 12X53	EACH	4		4			
51500100	NAME PLATES	EACH	1		1			

• SPECIALTY ITEM

 PATRICK ENGINEERING INC. 4970 VARSITY DRIVE LESLIE, IL 60532 patrickengineering.com	USER NAME = kkooppen(Rdwg-L121e) PLOT CONFIG = PDF(Grey-Small).plt PLOT SCALE = 1:100 PLOT DATE = 2/18/2013 4:37:29 PM	DESIGNED - CPK DRAWN - MJP CHECKED - JAH DATE - 2/18/2013	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE. 2746 SECTION 1616B COUNTY COOK TOTAL SHEETS 404 SHEET NO. 9	60J14
	SCALE: NA SHEET S00-06 OF 36 STA. TO STA.	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT							