


SUMMARY OF QUANTITIES		UNIT	URBAN 901.FED. 101.STATE TOTAL	CONSTRUCTION CODE				
CODE NO.	ITEM DESCRIPTION			0003 RDWY	0010 BRIDGE	0021 SIGNALS LIGHTING	0031 LNDSCP	0040 RET. WALL
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	2,521	2,521				
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	31	31				
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	89	89				
55100500	STORM SEWER REMOVAL 12"	FOOT	1,209	1,209				
55200200	STORM SEWER JACKED IN PLACE, 12"	FOOT	87	87				
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1				
58700300	CONCRETE SEALER	SQ FT	12,025		12,025			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	1,182		841			341
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	4	4				
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1	1				
60107700	PIPE UNDERDRAINS 6"	FOOT	448	448				
60107800	PIPE UNDERDRAINS 8"	FOOT	213	213				

• SPECIALTY ITEM

 PATRICK ENGINEERING INC. 4970 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	USER NAME = kwoepfen@dwg.Lisle/	DESIGNED - CPK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.U. RTE. 2746	SECTION 1616B	COUNTY COOK	TOTAL SHEETS 404	SHEET NO. 11
	PLOT CONFIG = PDF(Grey_Small).plt	DRAWN - MJP	REVISIONS -		SCALE: NA	SHEET SOQ-08 OF 36	STA. TO STA.	ILLINOIS FED. AID PROJECT			
PLOT SCALE = 1:100	CHECKED - JAH	REVISIONS -	DATE = 2/18/2013 4:37:48 PM	DATE = 2/18/2013	REVISIONS -	60J14					