

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY STATE 0005				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1609	1609				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	900	900				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1423	1423				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	501	501				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	50 FT	2125	2125				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	50 FT	472	472				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	61179	61179				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1609	1609				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	900	900				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1423	1423				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	501	501				

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY STATE 0005				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	900	900				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	647	647				
* 81028730	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/4" DIA.	FOOT	52	52				
* 81028770	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3" DIA.	FOOT	46	46				
* 81400200	HEAVY-DUTY HANDHOLE	EACH	1	1				
* 87900200	DRILL EXISTING HANDHOLE	EACH	3	3				
* 88600100	DETECTOR LOOP, TYPE I	FOOT	217	217				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2230	2230				
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	35	35				
* X0301242	PIEZO AXLE SENSOR, CLASS II	FOOT	22	22				
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	235	235				
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22				
* X8730810	ELECTRIC CABLE IN CONDUIT, CONOGA-30003	FOOT	211	211				

13 * Specialty Items