URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3162	3162					
21400100	GRADING AND SHAPING DITCHES	FOOT	2175	2175					
25200110	SODDING, SALT TOLERANT	SQ YD	3162	3162					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	50	50					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	154	154					
40600300	AGGREGATE (PRIME COAT)	TON	769	769					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	289	289					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	10575	10575					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	825	825					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	256	256					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	6	6					

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE 0005					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	21533	21533					
42001300	PROTECTIVE COAT	SQ YD	6325	6325					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	50	50					
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	192259	192259					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	100	100					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1522	1522					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	854	854					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	100	100					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	370	370					
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	7	7					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	112	112					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	27	27					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	13	13					

FILE NAME = c:\pw_work\pwidot\czrzasdr\d0245762\D07111-sht-plan.dgn	USER NAME = czrzasdr	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/20/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILL. 72 / ILL. 83
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341	31R-RS-1	COOK	36	3
		CONTRACT NO. 60M10		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT