

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE 0005				
* 78000500	THERMOPLASTIC PAVEMENT MARKING	FOOT	1544	1544				
	- LINE 8"							
* 78000600	THERMOPLASTIC PAVEMENT MARKING	FOOT	2872	2872				
	- LINE 12"							
* 78000650	THERMOPLASTIC PAVEMENT MARKING	FOOT	1220	1220				
	- LINE 24"							
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2451	2451				
78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2206	2206				
	REMOVAL							
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3792	3792				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL,	SO YD	3168	3168				
	VARIABLE DEPTH							
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	19950	19950				
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	3960	3960				
X6030310	FRAMES AND LIDS TO BE ADJUSTED	EACH	40	40				
	(SPECIAL)							
Z0004562	COMBINATION CONCRETE CURB AND GUTTER	FOOT	18973	18973				
	REMOVAL AND REPLACEMENT							
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	205	205				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE 0005				
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
* SPECIALTY ITEM								

FILE NAME :	USER NAME :	DESIGNED :	REVISED :
o:\pr-work\p100\ch2001\0245162\00711-01-plan\sign	chr2001	DRAWN :	REVISED :
		CHECKED :	REVISED :
		DATE :	REVISED :

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ILL. 72 / ILL. 83
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341	31R-RS-1	COOK	36	5
CONTRACT NO. 60M10				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				