


NOTES:

1. SEE DRAWING E-1 FOR ELECTRICAL SYMBOL LIST AND ABBREVIATIONS. SEE DRAWING E-2 FOR ELECTRICAL GENERAL NOTES.
2. INDICATES TEMPORARY PAVEMENT INSTALLATION LIMITS. SEE MAINTENANCE OF TRAFFIC DRAWINGS FOR CONSTRUCTION STAGING INFORMATION.
3. CONTRACTOR MUST CONFIRM THE BOLT CIRCLE DIAMETER FOR ALL EXISTING LIGHTING UNITS TO BE REMOVED AND RELOCATED PRIOR TO REMOVAL OF EXISTING POLE AND CONCRETE FOUNDATION.
4. CONTRACTOR MUST COORDINATE THE REMOVAL AND REINSTALLATION OF LIGHT POLE WITH THE PROPOSED RECONSTRUCTION OF 151st STREET AND WITH THE OWNER. SEE MAINTENANCE OF TRAFFIC DRAWINGS FOR LaGRANGE ROAD CONSTRUCTION AND 151st STREET STAGING PLANS. CONTRACTOR TO DISCONNECT POWER SOURCE AT NEXT LIGHT POLE EAST OF POLE TO BE RELOCATED. THIS WORK SHALL BE PAID FOR UNDER THE "REMOVE AND RELOCATE EXISTING LIGHT STANDARD" AND THE "REMOVAL OF POLE FOUNDATION" PAY ITEMS. SEPARATE PAYMENT WILL NOT BE MADE.
5. EXISTING UNIT DUCTS, CABLE, AND CONDUITS THAT ARE NOT REMOVED AS PART OF THE GENERAL CONTRACT DEMOLITION WORK SHALL BE ABANDONED IN PLACE. IF REMOVAL OF ANY CABLES AND DUCTS IS REQUIRED, PAYMENT FOR THAT WORK SHALL BE INCLUDED IN THE "REMOVAL OF LIGHTING UNIT" PAY ITEM, AND NO SEPARATE PAYMENT WILL BE MADE.
6. CONTRACTOR SHALL REMOVE 40' POLES FROM LaGRANGE AND RELOCATE THEM TO THE SIDE STREETS. AFTER EXISTING STOCK OF 40' POLES IS DEPLETED, THEN SHORTER POLES CAN BE RELOCATED TO SIDE STREETS AWAY FROM LaGRANGE ROAD, IF NEEDED, AS SHOWN ON THE PLANS.

100 S. WACKER DR.
 SUITE 500
 CHICAGO, IL 60606
 TEL (312) 939-1000
 FAX (312) 939-4198
URS



FILE NAME = D160M61-SHT-E15.dgn	USER NAME = michal_bartusiewicz	DESIGNED - MAE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	151st STREET TEMPORARY LIGHTING AND DEMOLITION PLAN			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SHT_PLAN	PLOT SCALE = 100.000000' / in.	DRAWN - MAE	REVISED -					330	103R-4	COOK	877	426
	PLOT DATE = 3/15/2013	CHECKED - DAD	REVISED -		E-15			CONTRACT NO. 60M61				
		DATE - 03/13/2013	REVISED -		SCALE: 1"=50'	SHEET 6 OF 7 SHEETS	STA. 498+50.00 TO STA. 531+50.00	ILLINOIS FED. AID PROJECT				

D160M61-SHT-E15.dgn 3/15/2013 2:27:06 PM