

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3537	3537			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	868	868			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	447	447			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5204	5204			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	552	552			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3362	3362			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3537	3537			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	868	868			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	447	447			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	193	193			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3521	3521			
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	150	150			
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	97	97			
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	80	80			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	70	70			
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			

\*specialty Items

FILE NAME *	USER NAME * par/tyrol	DESIGNED -	REVISED -
C:\pwr\work\148\148\par/tyrol\02520179-0129-01-01-01.dwg		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2010-148-RS	WILL	30	4
CONTRACT NO. 60N24				
FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT				