

CONSTRUCTION CODE

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	URBAN
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	19,175	19,175	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	100	100	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	13,800	13,800	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	150	150	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	800	800	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	12,340	12,340	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	6	6	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	36,290	36,290	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	1,020	1,020	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	154,300	154,300	

* SPECIALTY ITEMS

COMPANY NAME: HRGreen
 PROJECT CONTACT: HRGreen.com
 CLIENT: 10/24/2012 8:55:51 AM
 DATE PLOTTED: 86100196.09 sum 10.000
 FILE NAME: 10/24/12
 PLOT DRIVER: PLOT.DWT
 PEN TABLE: S:\pdr\cfr\pen.tbl



USER NAME = sperrin	DESIGNED - CMH	REVISED -
	DRAWN - SMP	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TEH	REVISED -
PLOT DATE = 10/24/2012	DATE - 10/24/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
U.S. ROUTE 12 (OLD RAND RD/MAIN STREET TO FISH LAKE RD.)

SCALE: N.T.S. SHEET NO. 2 OF 4 SHEETS STA. NA TO STA. NA

F.A.P. RTG. 334	SECTION TR-RS-3	COUNTY LAKE	TOTAL SHEETS 52	SHEET NO. 4
FEG. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60N25	