SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE ROADWAY 0005 URBAN	✓				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	30	30					
25200110	SODDING, SALT TOLERANT	SQ YD	30	30					
25200200	SUPPLEMENTAL WATERING	UNIT	2.6	2.6					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	12.8	12.8					
40600300	AGGREGATE (PRIME COAT)	TON	61.3	61.3					
40600400	MIXTURE FOR CRACKS, JOINTS,	TON	27	27					
	AND FLANGEWAYS								
40600827	POLYMERIZED LEVELING BINDER (MACHINE	TON	643	643					
	METHOD), IL-4.75, N50								
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT	SQ YD	315	315					
	JOINT								
40600985	PORTLAND CEMENT CONCRETE SURFACE	SQ YD	584	584					
	REMOVAL - BUTT JOINT								
40601005	HOT-MIX ASPHALT REPLACEMENT OVER	TON	68	68					
	PATCHES								
40603340	HOT-MIX ASPHALT SURFACE COURSE,	TON	1549	1549					
	MIX "D", N70								
42001300	PROTECTIVE COAT	SQ YD	60	60					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		100% STATE ROADWAY 0005 URBAN					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY	SQ YD	5	5					
	PAVEMENT, 8 INCH								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5	SQ FT	327	327					
	INCH								
42400800	DETECTABLE WARNINGS	SQ FT	10	10					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1618	1618					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2	SQ YD	9977	9977					
	1/4"								
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	45	45					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	60	60					
44000600	SIDEWALK REMOVAL	SQ FT	150	150					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES,	SQ YD	406	406					
	3"								
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	366	366					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	146	146					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	413	413					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	11	11					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5					

* SPECIALTY ITEMS

Rev.

FILE NAME = c:\pw_work\pwidot\abreuah\d0251847\D3\51-sht-plan.dgn	USER NAME = abreuah	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / In.	CHECKED -	REVISED -
	PLOT DATE = 12/14/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US 6 /IL ROUTE 53 (JACKSON ST. TO OSGOOD ST.)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
112	2010-153-RS	WILL	30	3
		CONTRACT NO. 60N45		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

D1351Lsht-plan.dgn 12/14/2012 9:18:55 AM User:abreuah