

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE ROADWAY 0005 URBAN				
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	5	5				
60600605	CONCRETE CURB, TYPE B	FOOT	10	10				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	60	60				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	800	800				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	309	309				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1587	1587				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2335	2335				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		100% STATE ROADWAY 0005 URBAN				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	702	702				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	115	115				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	264	264				
*72000100	SIGN PANEL-TYPE I	SQ FT	25	25				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	220	220				
*72900200	METAL POST-TYPE B	SQ FT	58	58				
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	309	309				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1587	1587				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2335	2335				
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	702	702				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	115	115				
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	264	264				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	174	174				

* SPECIALTY ITEMS

FILE NAME :	USER NAME : cbrugh	DESIGNED -	REVISED -
C:\p\work\p104\0251047\031511.dwg		DRAWN -	REVISED -
	PLOT SCALE : 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE : 12/14/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US 6 /IL ROUTE 53 (JACKSON ST. TO OSGOOD ST.)
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 112	SECTION 2010-153-RS	COUNTY WILL	TOTAL SHEETS 30	SHEET NO. 4
CONTRACT NO. 60N45				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev