SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY (URBAN 100% STATE)	CONSTRUCTION TYPE CODE: ROADWAY 0005	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	28	28	
20400800	FURNISHED EXCAVATION	CU YD	60	60	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	133	133	
21400100	GRADING AND SHAPING DITCHES	FOOT	100	100	
25000210	SEEDING, CLASS 2A	ACRE	0.03	0.03	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	3	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3	
25100630	EROSION CONTROL BLANKET	SQ YD	162	162	
25200110	SODDING, SALT TOLERANT	SQ YD	133	133	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7	
40600300	AGGREGATE (PRIME COAT)	TON	43	43	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	428	428	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	113	113	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	930	930	
42001300	PROTECTIVE COAT	SQ YD	14	14	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	10,236	10,236	
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	35	35	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	115	115	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	170	170	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	35	35	
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	15	15	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	104	104	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	7	
60404950	FRAMES AND GRATES, TYPE 24	EACH	1	1	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	50	50	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	797	797	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	232	232	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11,215	11,215	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	352	352	

35

CODE NO.	ITEM	UNIT	TOTAL QUANTITY (URBAN 100% STATE)	CONSTRUCTION TYPE CODE: ROADWAY 0005	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	157	157	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	118	118	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,307	4,307	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	232	232	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,215	11,215	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	352	352	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	157	157	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	118	118	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	117	117	
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	117	117	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	257	257	
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	30	30	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1	
X6330104	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE I SPECIAL, FLARED	EACH	1	1	
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	80	80	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

18

* SPECIALTY ITEMS

Stantec

USER NAME = dpteroszek	DESIGNED - DLP	REVISED -	
	DRAWN - STANTEC	REVISED -	
PLOT SCALE = 50.00 ' / IN.	CHECKED - TMH	REVISED -	
PLOT DATE = 12/11/2012	DATE - 12/11/2012	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 120 ROADWAY RESURFACING
SUMMARY OF QUANTITIES

SCALE: 50.00 ' / IN. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
342	2010-154-RS	LAKE	20	3
		CONTRACT NO. 60N55		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT