

**URBAN**

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0005	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16	
40600300	AGGREGATE (PRIME COAT)	TON	77	77	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	29	29	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	807	807	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	214	214	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	93	93	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1614	1614	
42001300	PROTECTIVE COAT	SO YD	267	267	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	19209	19209	
44002208	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2"	SO YD	825	825	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	20	20	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	360	360	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	200	200	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	245	245	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	28	28	
60404950	FRAMES AND GRATES, TYPE 24	EACH	10	10	
60406000	FRAMES AND LIDS, TYPE I, OPEN LID	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
<del>70100460</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701306</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4024	4024	

**URBAN**

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 0005	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	472	472	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11336	11336	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1773	1773	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	617	617	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	149	149	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	472	472	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11336	11336	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1773	1773	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	617	617	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	149	149	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	264	264	
78300100	PAVEMENT MARKING REMOVAL	SO FT	1618	1618	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	264	264	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	256	256	
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	150	150	
X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	150	150	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4	4	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	28	28	
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	318	318	
Z0004562	COMBINATION CURB AND GUTTER REMOVE AND REPLACEMENT ↑ CONCRETE	FOOT	800	800	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1342	1342	

\* SPECIALTY ITEMS



DESIGNED - MJJ	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJJ, SLV	REVISED -
DATE - 12/11/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
IL 131 (GREEN BAY ROAD) FOREST VIEW DR TO ROCKLAND RD**

SCALE: NONE    SHEET NO. 1 OF 1 SHEET    STA. 3+17.50 TO STA. 51+50

F.A.J. RTE. 2711	SECTION K-1-R-RS	COUNTY LAKE	TOTAL SHEETS 21	SHEET NO. 3
D-91-327-11			CONTRACT NO. 60N57	
FED. ROAD DIST. NO.    ILLINOIS FED. AID PROJECT				

Rev.