


PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN 100% STATE ROADWAY 0005	
			TOTAL QUANTITY	ROADWAY 0005
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	100	100
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	211	211
40600300	AGGREGATE (PRIME COAT)	TON	1,057	1,057
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	452	452
40600895	CONSTRUCTING TEST STRIP	EACH	3	3
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	287	287
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	29,467	29,467
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	25,467	25,467
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8,221	8,221
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	73,408	73,408
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3,875	3,875
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	661	661
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	11,780	11,780
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	8,200	8,200
60402110	GRATES, TYPE 7	EACH	1	1
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FOOT POSTS	FOOT	200	200
63200310	GUARDRAIL REMOVAL	FOOT	200	200
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	118,797	118,797
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1

70

H:\Jobs\2009\20093023-47\CAD\Site\dgm\00\060663-sht-500.dgn
 12/10/2012 2:01:50 PM



USER NAME * 1485	DESIGNED - EF	REVISED -
PLOT SCALE * 100.0000 / 1 in.	DRAWN - EF	REVISED -
PLOT DATE * 12/10/2012	CHECKED - RS	REVISED -
	DATE - 12-20-2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 394 STEGER ROAD TO S. OF ELMSCOURT LANE
SUMMARY OF QUANTITIES

SCALE: 1"=50' SHEET 1 OF 3 SHEETS STA. TO STA.

P.A.P. RTE. 332	SECTION 10A-RS-2	COUNTY WILL	TOTAL SHEETS 28	SHEET NO. 3
CONTRACT NO. 60N63				
ILLINOIS FED. AID PROJECT				

**Specialty Items*