



PAVEMENT MARKING LEGEND

- 1 THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE SOLID
- 2 THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW SOLID
- 3 THERMOPLASTIC PAVEMENT MARKING - LINE 4" DOUBLE YELLOW, 2 @ 11" C-C W/ 2 AMBER 2-WAY RPM'S, 80' C-C
- 4 THERMOPLASTIC PAVEMENT MARKING - LINE 5" WHITE SKIP DASH 10' DASH, 30' SKIP W/2 CRYSTAL/OPAQUE RPM, 80' C-C
- 5 THERMOPLASTIC PAVEMENT MARKING - LINE 6" WHITE
- 6 THERMOPLASTIC PAVEMENT MARKING - LINE 12" WHITE @ 45 DEGREE, 500' C-C
- 7 THERMOPLASTIC PAVEMENT MARKING - LINE 12" YELLOW @ 45 DEGREE, 500' C-C
- 8 THERMOPLASTIC PAVEMENT MARKING - LINE 24" WHITE
- 9 THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS

H:\Jobs\2009\20093023-47\CAD\Site\ dgn\00\016063-sht-Plan06.dgn
 12/10/2012 2:01:54 PM

GRAEF 8501 N. Higgins Road Suite 280
 Chicago, Illinois 60631
 (773) 399-0112

USER NAME = 1485	DESIGNED - EF	REVISED -
	DRAWN - EF	REVISED -
PLOT SCALE = 100.0018' / 1"	CHECKED - RS	REVISED -
PLOT DATE = 12/10/2012	DATE - 12-20-2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 394 STEGER ROAD TO S. OF ELMSCOURT LANE ROADWAY AND PAVEMENT MARKING PLANS			
SCALE: 1"=50'	SHEET 6	OF 12 SHEETS	STA. 2146+00 TO STA. 2174+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	10A-RS-2	WILL	28	12
CONTRACT NO. 60N63				
ILLINOIS FED. AID PROJECT				