

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	
				ROADWAY	
				0005	URBAN
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28,900	28,900	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,970	3,970	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	580	580	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	3,760	3,760	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	420	420	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	430	430	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,083	2,083	
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1,560	1,560	
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	2,400	2,400	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	179	179	
X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	985	985	
XZ043900	PREFORMED JOINT FILLER REMOVAL	FOOT	9,000	9,000	
Z0038123	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/2"	SQ YD	798	798	
Z0004562	COMBINATION CONCRETE CURB & GUTTER REMOVAL AND REPLACEMENT	FOOT	4,164	4,164	
Z0017800	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED (SPECIAL)	EACH	5	5	

* SPECIALTY ITEMS

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: HRGreen.com
 CLIENT: HRGreen.com
 DATE PLOTTED: 2/6/2013 9:46:02 PM
 PLOT SCALE: N/A
 PLOT DATE: 2/6/2013



USER NAME: spenal	DESIGNED - CMH	REVISED -
	DRAWN - SMP	REVISED -
	CHECKED - TEH	REVISED -
	DATE - 2/6/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 4 OF 5 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2011-080-RS	COOK	44	6
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 60R07