	SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE	0005 65% STATE BENSENVILLE 35%	0005 100% BENSENVILLE			
	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	20	20					
	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	20	20					
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4014	4014					
*	21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	12,041	12,041					
*	25000210	SEEDING, CLASS 2A	ACRE	2.49	2.49					
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	224	224					
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	224	224					
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	224	224					
*	25100630	EROSION CONTROL BLANKET	SQ YD	12,041	12,041					
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	206	206					
	40600300	AGGREGATE (PRIME COAT)	TON	1026	1026					
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	385	385					
	40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	13879	13879					
	40600895	CONSTRUCTING TEST STRIP	EACH	3	3					

	SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE	0005 65% STATE BENSENVILLE 35%	0005 100% BENSENVILLE			
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	568	568					
	40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1269	1269					
	40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	19,150	19,150					
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10155	10155					
	42001300	PROTECTIVE COAT	SQ YD	1220	1220					
	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	256259	256259					
	~~44000500~~	~~COMBINATION CURB AND GUTTER REMOVAL~~	~~FOOT~~	~~4523~~	~~4523~~					
	44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SQ YD	9058	9058					
	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	6694	6694					
	44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	328	328					
	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	854	854					
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	936	936					
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4	4					

* Specialty Items

Rev.

FILE NAME = c:\pw_work\pwidot\reichenbach\d031560b\D400313-sht\standgn	USER NAME = reichenbach	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 2/20/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 83 (IL 19 TO IL 64)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	540R-RS-3	DUPAGE	38	3

CONTRACT NO. 60V54

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT