

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE	0005 65% STATE BENSENVILLE 35%	0005 100% BENSENVILLE			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	142	142					
<del>60603800</del>	<del>COMBINATION CONCRETE CURB AND CUTTER, TYPE B-G-12</del>	<del>FOOT</del>	<del>4523</del>	<del>4523</del>					
<del>60619600</del>	<del>CONCRETE MEDIAN, TYPE SB-G-12</del>	<del>SQ FT</del>	<del>1048</del>	<del>1048</del>					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	28102	28102					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	728	728					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	70099	70099					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2112	2112					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	27683	27683					

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE	0005 65% STATE BENSENVILLE 35%	0005 100% BENSENVILLE			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	11300	11300					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	476	476					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3120	3120					
X 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	728	728					
X 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	70099	70099					
X 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2112	2112					
X 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	27683	27683					
X 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	11300	11300					
X 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	476	476					
X 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1415	1415					
X 78200530	BARRIER WALL MARKERS, TYPE C	EACH	224	224					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1415	1415					

12. \*Specialty Items

FILE NAME : c:\p\work\1111\velchencb\110315608\100313-1111.dwg	USER NAME : velchencb	DESIGNED - DRAWN -	REVISED - REVISED -
PLOT SCALE : 1000000' = 1"	CHECKED -	REVISED -	REVISED -
PLOT DATE : 2/20/2013	DATE -	REVISED -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 83 (IL 19 TO IL 64)  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 344	SECTION 540R-RS-3	COUNTY DU PAGE	TOTAL SHEETS 38	SHEET NO. 4
CONTRACT NO. 60V54				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				