

90% FED.
10% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY 0004 URBAN	URBAN BRIDGE 0014 SN 016-2437	TRAFFIC SIGNALS 0021 URBAN
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,278	1,278		
40600300	AGGREGATE (PRIME COAT)	TON	24	24		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	356	356		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	166	166		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	626	626		
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	906	906		
44000100	PAVEMENT REMOVAL	SQ YD	1,442	1,442		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	3,099	3,099		
44000300	CURB REMOVAL	FOOT	76	76		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,069	1,069		
44003100	MEDIAN REMOVAL	SQ FT	2,202	2,202		
44004250	PAVED SHOULDER REMOVAL	SQ YD	844	844		
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	39	39		

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



FILE NAME *	USER NAME * default	DESIGNED -	REVISED -
FILE #		DRAWN - OC	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - RCR	REVISED -
	PLOT DATE = 12/7/2012	DATE - 11/08/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 3 OF 19 SHEETS STA. TO STA.

F.A.I. RTE. 94	SECTION 2012-060-BR	COUNTY COOK	TOTAL SHEETS 285	SHEET NO. 5
CONTRACT NO. 60V61			ILLINOIS FED. AID PROJECT	

S:\272\ASL\COOK\60V61_SHEETS\03BR61-A11-10a.dgn