

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004 URBAN	URBAN BRIDGE 0014 SN 016-2437	TRAFFIC SIGNALS 0021 URBAN
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	9	9		
* 83050715	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 6 FT. DAVIT ARM	EACH	7	7		
* 83050825	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. DAVIT ARM	EACH	2	2		
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	19	19		
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	2	2		
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	26	26		
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	26	26		
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2			2
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	843			843
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2			2
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2,160	2,160		
* K0029632	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL	GALLON	2.5	2.5		
* K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	6	6		
* K0036120	MULCH PLACEMENT 4"	SO YD	262	262		

*Specialty Items

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



FILE NAME *	USER NAME * default	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE. 94	SECTION 2012-060-BR	COUNTY COOK	TOTAL SHEETS 285	SHEET NO. 13
FILE#	PLOT SCALE * #SCALE#	DRAWN - OC	REVISED -		SCALE: NA	SHEET NO. 11 OF 19 SHEETS	STA.	TO STA.	CONTRACT NO. 60V61				
	PLOT DATE * 12/7/2012	CHECKED - RGR	REVISED -		ILLINOIS FED. AID PROJECT								
		DATE - 11/08/2012	REVISED -										

S:\1072\052_CAD\01050161_Sheet\01050161.dwg