

90% FED.  
10% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY 0004 URBAN	URBAN BRIDGE 0014 SN 016-2437	TRAFFIC SIGNALS 0021 URBAN
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	8	8		
* Z0033038	CONTROLLER, TRAFFIC, 16 LOAD BAY, P CABINET	EACH	2			2
Z0034806	MODULAR EXPANSION JOINT-SWIVEL 6"	FOOT	50		50	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	25		25	
Z0062456	TEMPORARY PAVEMENT	SQ YD	6,966	6,966		
Z0064800	SELECTIVE CLEARING	UNIT	1.3	1.3		
Z0065745	SLOTTED DRAIN 12" WITH 2 1/2" SLOT	FOOT	610	610		
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	40		40	
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	12	12		
✓ X0370001	TRENCH BACKFILL WITH SCREENINGS (CDOT)	FOOT	1,909			1,909
✓ X0370008	JUNCTION BOX, NON-METALLIC, EMBEDDED IN STRUCTURE, 21" X 11" X 8"	EACH	2	2		
* X0370002	BREAK DOWN STREET LIGHT FOUNDATION (CDOT)	EACH	2	2		
✓ X0370003	ELECTRIC CABLE IN CONDUIT, TRIPLEX, 2 1/C NO.6, 1/C NO.8 (CDOT)	FOOT	874	874		
✓ X0370004	LUMINAIRE, STREET LIGHT, HPS, 400 WATT, 240 VOLT, ARTERIAL, SEMI-CUTOFF (CDOT)	EACH	6	6		

\* Specialty Items

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com



FILE NAME	USER NAME	DESIGNED	REVISIONS	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SCALE	12/27/2012	DRAWN - OC	CHECKED - RGR	DATE - 11/08/2012	REVISIONS	SCALE: NA	SHEET NO. 16 OF 19 SHEETS	STA.	TO STA.	94	2012-060-BR	COOK	285	18
											CONTRACT NO. 60V61			
											ILLINOIS FED. AID PROJECT			

SCALE: 1/8" = 1'-0" (SEE SHEET 18)