

SCHEDULE OF CLEANING AND TELEVISION OF SEWERS (CONTINUED)

EXISTING PIPE NO.	LOCATION	FROM STATION	OFFSET	TO STATION	OFFSET	DIAMETER (INCHES)	X0325207	X5537600	X5537700	X5537800	X5537900	X5538000	X5538200	X5538600	X5538700
							TV INSPECT OF SEWER (FOOT)	SS CLEANED 8" (FOOT)	SS CLEANED 10" (FOOT)	SS CLEANED 12" (FOOT)	SS CLEANED 15" (FOOT)	SS CLEANED 18" (FOOT)	SS CLEANED 24" (FOOT)	SS CLEANED 36" (FOOT)	SS CLEANED 42" (FOOT)
CT-51	103RD ST	35+77.3	44.5' RT	35+74.9	25.4' RT	8	16.2	16.2							
CT-52	103RD ST	35+77.1	44.5' LT	35+72.3	25.4' RT	8	67.2	67.2							
CT-53	103RD ST	35+81.2	159.9' LT	35+77.1	44.5' LT	8	111.4	111.4							
CT-54	103RD ST	35+50.1	110.7' LT	35+79.0	99.9' LT	8	29.7	29.7							
CT-55	103RD ST	EB LANES	44.6' RT	EB LANES	27.5' RT	8	16.0	16.0							
CT-56	103RD ST	WB LANES	44.3' LT	EB LANES	27.5' RT	8	70.5	70.5							
CT-57	103RD ST	EB LANES	42.6' RT	EB LANES	29.1' RT	8	37.4	37.4							
CT-58	103RD ST	WB LANES	42.6' LT	EB LANES	17.5' RT	8	59.5	59.5							
CT-59	103RD ST	EB LANES	39.0' RT	EB LANES	18.5' RT	8	65.1	65.1							
CT-60	103RD ST	WB LANES	40.6' LT	CENTERLINE	0.0' RT	8	36.0	36.0							
CT-61	103RD ST	EB LANES	33.8' RT	CENTERLINE	0.0' RT	8	36.0	36.0							
CT-62	103RD ST	WB LANES	34.4' LT	CENTERLINE	0.0' RT	8	35.6	35.6							
CT-63	103RD ST	EB LANES	19.7' RT	CENTERLINE	0.0' RT	8	20.7	20.7							
CT-64	103RD ST	EB LANES	29.0' RT	EB LANES	19.7' RT	8	9.4	9.4							
CT-65	103RD ST	WB LANES	20.3' LT	CENTERLINE	0.0' RT	8	20.5	20.5							
CT-66	EB STNY LINE E	925+88.2	122.4' LT	926+73.8	126.6' LT	12	81.7		81.7						
CT-67	EB STNY LINE F	926+75.9	131.9' RT	927+22.6	163.0' RT	15	52.1		52.1						
CT-68	EB STNY LINE F	926+12.9	129.9' RT	926+75.9	131.9' RT	10	59.0	59.0							
TOTAL							6663.0	1332.9	172.0	1054.3	1141.6	417.2	309.3	1427.1	808.6

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbandainc.com



FILE NAME =	USER NAME = default	DESIGNED - JAM	REVISED -
*FILEL*		DRAWN - JAM	REVISED -
	PLOT SCALE = *SCALE*	CHECKED - RGR	REVISED -
	PLOT DATE = 12/7/2012	DATE - 11/08/2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

DRAINAGE SCHEDULES

SCALE: SHEET NO. 4 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-060-BR	COOK	285	95A
CONTRACT NO. 60V61				
ILLINOIS FED. AID PROJECT				

S:\1072-05-CADD\1068061\_Sheets\1068061-shs-schedule.dwg