



- 1 - 96 FIBER OPTIC TRUNK CABLE IN 1 1/4" DIA. INNER DUCT (TYP.)
- 1 - 96 FIBER OPTIC DISTRIBUTION CABLE IN 1 1/4" DIA. INNER DUCT (TYP.)

UNDERGROUND CONDUIT,
GALVANIZED STEEL, 4" DIA., 83'

SINGH
SINGH & ASSOCIATES, INC.
CONSULTING ENGINEERS

FILE NAME = J:\293\Task-3\CD\CAD Sheets\60V83\10V83-sh13-1T9.dgn	USER NAME = _USER_	DESIGNED - OB	REVISED -
		DRAWN - AM/WC	REVISED -
	PLOT SCALE = 50.0000' / in.	CHECKED - AG	REVISED -
	PLOT DATE = 12/19/2012	DATE - 12/21/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

FIBER OPTIC CABLE INSTALLATION PLAN I-94

SCALE: 1"=50' SHEET 9 OF 11 SHEETS STA. 372+00 TO STA. 387+00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-0731	COOK	25	13
CONTRACT NO. 60V83				
ILLINOIS FED. AID PROJECT				