

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	11					
40600300	AGGREGATE (PRIME COAT)	TON	53	53					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1473	1473					
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	198	198					
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	119	119					
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	79	79					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	77	77					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	23	23					
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	9702	9702					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10788	10788					

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1222	1222					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	20	20					
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	6	6					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
Z0038121	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2"	SO YD	13149	13149					

* SPECIALTY ITEMS
 NON-PARTICIPATING ITEMS

FILE NAME	USER NAME	DESIGNED	REVISED
DRAWN	CHECKED	DATE	REVISED
PLOT SCALE = 1/4" = 100'		PLOT DATE = 3/14/2013	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
F.A.I. 55/ 1-55 (STEVENS ON EXPY.)--KEDZIE AVE. TO CALIFORNIA AVE.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2012-087-1	COOK	18	3
SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 60W08	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				