



PROPOSED TYPICAL SECTION
STA. 38+38 TO 67+23

****NOTE:**
 PROPOSED RUMBLE STRIPS
 - NORTHBOUND I-55
 STA. 24+36 TO STA. 72+11
 - SOUTHBOUND I-55
 STA. 22+84 TO STA. 72+11

LEGEND:

- ① EXIST. P.C.C. PAVEMENT, ±12"
 - ② EXIST. AGGREGATE SUBGRADE, 12"
 - ③ EXIST. GRANULAR SUB-BASE
 - ④ EXIST. BARRIER WALL
 - ⑤ EXIST. BARRIER WALL REFLECTORS, TYPE B
 - ⑥ EXIST. PIPE UNDERDRAIN, 6"
 - ⑦ EXIST. AGGREGATE SHOULDER
 - ⑧ EXIST. RUMBLE STRIP
 - ⑨ EXIST. MEDIAN DITCH GRADE
 - ⑩ EXIST. TIE BARS
 - ⑪ EXIST. GUARDRAIL
 - ⑫ PROP. P.C.C. SURFACE REMOVAL, 2"
 - ⑬ PROP. HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 2"
 - ⑭ PROP. GRADING AND SHAPING SHOULDERS
 - ⑮ PROP. AGGREGATE WEDGE SHOULDERS, TYPE B
 - ⑯ PROP. RUMBLE STRIPS
- R CURB AND GUTTER REMOVAL AND REPLACEMENT

FILE NAME =	USER NAME = steedpa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING AND PROPOSED TYPICAL SECTIONS		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\pwwdot\stedpa\0329685\0116413-sht-plan.dgn		DRAWN -	REVISED -		F.A.I. 55/ I-55 (STEVENS ON EXPY.)--KEDZIE AVE. TO CALIFORNIA AVE.		55	2012-087-1	COOK	18	7
		CHECKED -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 60W08		
		DATE -	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT						