SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE ROADWAY 0005					
CODE NO	ITEM	UNIT							
70300100	SHORT TERM PAVEMENT MARKING	FOOT	42126	42126					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	3760	3760					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	33092	33092					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	14841	14841					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	388	388					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1312	1312					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1567	1567					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14042	14042					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3760	3760					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33092	33092					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	14848	14848					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	388	388					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1312	1312					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE ROADWAY 0005					
CODE NO	ITEM	UNIT							
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1567	1567					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2121	2121					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	168	168					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1273	1273					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	5452	5452					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	14	14					
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	46	46					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	975	975					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
~~Z0076600~~	~~TRAINEES~~	~~HOUR~~	~~1000~~	~~1000~~					
Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	1000	1000					

⊙ 0042

Rev.

* SPECIALITY ITEMS

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 2/15/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

79TH ST.
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 2 OF 2 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1548	461RS-3	COOK	38	4

CONTRACT NO. 60W15

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT