

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				HPP FUNDS									
				80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	100% LOCAL		
				ROADWAY 0003 URBAN	BRIDGE 0008 URBAN	BRIDGE 0011 URBAN	ENVIRONMENTAL 0020 URBAN	SAFETY 0021 URBAN	LANDSCAPING 0031 URBAN	SPECIAL BRIDGE 0040 URBAN	ROADWAY 0003 URBAN		
• 25000775	SELECTIVE MOWING STAKES	EACH	11							11			
• 25100115	MULCH, METHOD 2	ACRE	5.75							5.75			
• 25100630	EROSION CONTROL BLANKET	SO YD	14398							14398			
• 25200200	SUPPLEMENTAL WATERING	UNIT	10							10			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1056				1056						
28000305	TEMPORARY DITCH CHECKS	FOOT	578				578						
28000400	PERIMETER EROSION BARRIER	FOOT	7667				7667						
28000500	INLET AND PIPE PROTECTION	EACH	9				9						
28000510	INLET FILTERS	EACH	113				113						
28001100	TEMPORARY EROSION CONTROL BLANKET	SO YD	14398				14398						
28100105	STONE RIPRAP, CLASS A3	SO YD	108				108						
28100107	STONE RIPRAP, CLASS A4	SO YD	399			399							
28200200	FILTER FABRIC	SO YD	565			457	108						
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	43985	43985									

• SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...General\163598-shr-coq-02.dgn	DRAWN - TMB	REVISED -
USER NAME = toddblank	CHECKED - JMM	REVISED -
PLOT DATE = 1/18/2013	DATE - 01/18/2013	REVISED -



**STATE OF ILLINOIS
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 2 OF 21 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-18-RP	KANE	451	6
CONTRACT NO. 63598			ILLINOIS FED. AID PROJECT	