

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				HPP FUNDS									
				80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	100% LOCAL		
				ROADWAY 0003 URBAN	BRIDGE 0008 URBAN	BRIDGE 0011 URBAN	ENVIRONMENTAL 0020 URBAN	SAFETY 0021 URBAN	LANDSCAPING 0031 URBAN	SPECIAL BRIDGE 0040 URBAN	ROADWAY 0003 URBAN		
44000100	PAVEMENT REMOVAL	SO YD	29967	29967									
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	2188	2188									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1761	1761									
44003100	MEDIAN REMOVAL	SO FT	10423	10423									
44004250	PAVED SHOULDER REMOVAL	SO YD	4167	4167									
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	21	21									
44213100	PAVEMENT FABRIC	SO YD	476	476									
48101200	AGGREGATE SHOULDERS, TYPE B	TON	185	185									
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	639					639					
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1							
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1							
50105220	PIPE CULVERT REMOVAL	FOOT	126	126									
50200100	STRUCTURE EXCAVATION	CU YD	18			18							
50300225	CONCRETE STRUCTURES	CU YD	115.2			50.7					64.5		

* SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...General\16163098-shr-soq-04.dgn	DRAWN - TMB	REVISED -
USER NAME = toddblank	CHECKED - JMM	REVISED -
PLOT DATE = 1/18/2013	DATE - 01/18/2013	REVISED -



**STATE OF ILLINOIS
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 4 OF 21 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-10-RP	KANE	451	8
ILLINOIS FED. AID PROJECT			CONTRACT NO. 63598	