

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				HPP FUNDS									
				80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	100% LOCAL		
				ROADWAY 0003 URBAN	BRIDGE 0008 URBAN	BRIDGE 0011 URBAN	ENVIRONMENTAL 0020 URBAN	SAFETY 0021 URBAN	LANDSCAPING 0031 URBAN	SPECIAL BRIDGE 0040 URBAN	ROADWAY 0003 URBAN		
51203600	TEST PILE STEEL HP12X53	EACH	2		2								
51203900	TEST PILE STEEL HP14X89	EACH	5			5							
51204650	PILE SHOES	EACH	14		14								
51500100	NAME PLATES	EACH	2		1	1							
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3	3									
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	8	8									
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	267	267									
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	146	146									
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	3793	3793									
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	439	439									
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	785	785									
550A0400	STORM SEWERS, CLASS A TYPE 2 21"	FOOT	622	622									
550A0450	STORM SEWERS, CLASS A TYPE 2 36"	FOOT	430	430									
550A0640	STORM SEWERS, CLASS A TYPE 3 12"	FOOT	24	24									

* SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...general\ND163998-shr-soq-06.dgn	DRAWN - TMB	REVISED -
USER NAME = toddlark	CHECKED - JMM	REVISED -
PLOT DATE = 1/18/2013	DATE - 01/18/2013	REVISED -



**STATE OF ILLINOIS
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 6 OF 21 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-18-RP	KANE	451	10
CONTRACT NO. 63598				
ILLINOIS FED. AID PROJECT				