

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										
				HPP FUNDS										
				80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	100% LOCAL		
				ROADWAY 0003 URBAN	BRIDGE 0008 URBAN	BRIDGE 0011 URBAN	ENVIRONMENTAL 0020 URBAN	SAFETY 0021 URBAN	LANDSCAPING 0031 URBAN	SPECIAL BRIDGE 0040 URBAN	ROADWAY 0003 URBAN			
X0326401	BARRIER WALL REMOVAL	FOOT	115	115										
X0326694	PLUG EXISTING STORM SEWERS	CU YD	0.3	0.3										
X0327036	BIKE PATH REMOVAL	SQ YD	1685	1685										
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	177		177									
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2										
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6	6										
X4023000	TEMPORARY ACCESS (ROAD)	EACH	2	2										
X4024100	TEMPORARY ACCESS (WINTERIZE)	SQ YD	396	396										
X5020200	STRUCTURE EXCAVATION (SPECIAL)	CU YD	1019			1019								
X5030225	CONCRETE STRUCTURES (SPECIAL)	CU YD	388.2			388.2								
X5120005	DRIVING PILES (SPECIAL)	FOOT	5705			5705								
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	4670								4670			
X5510100	STORM SEWER REMOVAL	FOOT	1484	1484										
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	279	279										

• SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED -
...General\10163598-shr-soq-17.dgn	DRAWN - TMB	REVISED -
USER NAME = toddblank	CHECKED - JMM	REVISED -
PLOT DATE = 1/18/2013	DATE - 01/18/2013	REVISED -



**STATE OF ILLINOIS
DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 17 OF 21 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-18-RP	KANE	451	21
CONTRACT NO. 63598				
ILLINOIS FED. AID PROJECT				