

PAVEMENT SCHEDULE

LOCATION			40701931	42000501	21001000	40701901	40600100	30300112	40603335	35101800	42001300	44213100	44201345
			HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 12 1/2"	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 11"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE SUBGRADE IMPROVEMENT 12"	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	AGGREGATE BASE COURSE, TYPE B, 6"	PROTECTIVE COAT	PAVEMENT FABRIC	CLASS D PATCHES, TYPE III, 9 INCH
ROAD	Station From	Station To	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(GAL)	(SQ YD)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
IL 25	102+52.19	106+90.80	2,169	0	2,472	0	1,085	0	0	0	0	0	0
IL 25	106+90.80	108+86.28	0	1,284	1,607	0	0	0	0	0	2568	0	0
IL 25/STEARNS RD.	108+86.28	112+62.41	0	2,384	2,815	0	0	0	0	0	4768	0	21
IL 25/STEARNS RD.	112+62.41	117+90.41	0	3,267	2,384	0	0	0	0	0	6534	0	0
IL 25/STEARNS RD.	118+12.83	123+00.00	0	3,170	4,124	0	0	0	0	0	6340	0	0
IL 25/STEARNS RD.	123+00.00	125+00.00	0	2,263	3,952	0	0	0	0	0	4526	0	0
IL 25/STEARNS RD.	125+00.00	130+99.77	0	4,633	2,544	0	0	0	0	0	9266	0	0
IL 25/STEARNS RD.	130+99.77	132+00.00	0	1,513	5,582	0	0	0	0	0	3026	0	0
IL 25/STEARNS RD.	132+00.00	142+40.13	0	8,087	9,652	0	0	0	0	0	16174	0	0
STEARNS RD	606+39.23	608+92.86	0	2,784	3,655	0	0	0	0	0	5568	0	0
GILBERT ST	301+18.91	307+80.42	0	0	3,134	2606	1,303	0	0	0	0	0	0
DUNHAM RD	142+40.13	146+93.87	0	703	1,931	0	0	0	0	0	1406	0	0
MULTI USE PATH	577+64.00	597+00.00	0	0	133	0	0	0	210	2,048	0	0	0
IL 25/STEARNS RD./CCPRR GRADE CROSSING			132	0	0	0	0	0	0	0	0	476	0
RELOCATED FOREST PRESERVE PATH			0	0	0	0	0	0	0	354			
DRIVEWAYS			0	0	0	0	452	0	132	0	0	0	0
TEMPORARY PAVEMENT			0	0	0	0	1,597	0	0	3,111	0	0	0
			2,302	30,088	43,985	2,606	4,437	0	342	5,513	60,176	476	21

CURB AND GUTTER SCHEDULE

LOCATION			60605000	60610400	42001300
			COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	PROTECTIVE COAT
ROAD	Station From	Station To	(FOOT)	(FOOT)	(SQ YD)
IL 25	102+52.13	106+90.80	986		548
IL 25	106+90.80	108+86.28	346		194
IL 25/STEARNS RD	108+86.28	112+62.41	804		448
IL 25/STEARNS RD	112+62.41	CCPRR	2,125	150	1266
IL 25/STEARNS RD	CCPRR	123+00.00	1,949	150	1168
IL 25/STEARNS RD	123+00.00	125+00.00	699		390
IL 25/STEARNS RD	125+00.00	130+99.77	2,060		1146
IL 25/STEARNS RD	130+99.77	132+00.00	271		152
IL 25/STEARNS RD	132+00.00	142+40.13	3,244		1804
IL 25/STEARNS RD	142+40.13	145+00.00	260		146
STEARNS RD	606+39.23	608+92.86	1072		596
GILBERT ST	301+18.91	307+80.42	1323		736
DUNHAM RT TURN LANE	145+00.00	146+53.24	257		144
			15,396	300	8,738

MEDIAN & ISLAND SCHEDULE

LOCATION			X6061100	42001300	60625900	60625600
			CONCRETE MEDIAN, TYPE SB (SPECIAL)	PROTECTIVE COAT	P.C.C. RAMPED MEDIAN TERMINAL	ISLAND PAVEMENT (6")
ROAD	Station From	Station To	(SQ FT)	(SQ YD)	(EACH)	(SQ YD)
IL 25/STEARNS RD	106+90.80	108+86.28	1,769	348		138
IL 25/STEARNS RD	129+30.00	130+97.00	999	224		
IL 25/STEARNS RD	132+20.00	134+00.00	1,058	240		
IL 25/STEARNS RD	143+68.00	144+98.24	519	116		
STEARNS RD	605+95.78	607+27.74	860	192		
CCPRR - WEST SIDE				32	1	
CCPRR - EAST SIDE				32	1	
IL 25/STEARNS RD				1,956		978
IL 25/STEARNS RD				2,324		1,162
			5,206	5,464	2	2,278

DRIVEWAY SCHEDULE

LOCATION			35501316	40603335
			HOT-MIX ASPHALT BASE COURSE, 8"	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50
ROAD	STATION	SIDE	(SQ YD)	(TON)
IL 25	105+38.35	RT	134	12
IL 25	106+72.42	RT	376	35
IL 25/STEARNS RD	115+73.26	RT	82	9
IL 25/STEARNS RD	119+76.22	RT	53	7
IL 25/STEARNS RD	121+18.85	LT	59	7
IL 25/STEARNS RD	124+85.00	RT	61	6
GILBERT ST	302+25.00	RT	151	16
GILBERT ST	302+58.77	RT	88	10
GILBERT ST	304+12.58	RT	83	10
GILBERT ST	305+89.67	RT	174	20
			1,262	132