

### PAVEMENT MARKING SCHEDULE

LOCATION			78000100	78000200		78000400		78000800	78008200		78008210		78008230		78008240	78008250		78008270	78300100
			THERMOPLASTIC PAVT MARKING - LETTERS & SYMBOLS	THERMOPLASTIC PAVT MARKING - LINE 4"		THERMOPLASTIC PAVT MARKING - LINE 6"		THERMOPLASTIC PAVT MARKING - LINE 12"	POLYUREA PAVT MARKING TYPE I - LETTERS & SYMBOLS		POLYUREA PAVT MARKING TYPE I - LINE 4"		POLYUREA PAVT MARKING TYPE I - LINE 6"		POLYUREA PAVT MARKING TYPE I - LINE 8"	POLYUREA PAVT MARKING TYPE I - LINE 12"		POLYUREA PAVT MARKING TYPE I - LINE 24"	PAVEMENT MARKING REMOVAL
Road	Start STA	End STA	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
IL 25	102+52.19	106+90.80	---	1770	20	53	---	47	---	---	29	---	---	---	---	---	---	---	1368
IL 25/STEARNS RD	106+90.80	109+17	---	---	---	---	---	---	73	---	---	80	---	220	---	---	---	40	---
IL 25/STEARNS RD	110+62	118+00	---	---	---	---	---	---	73	123	---	370	---	313	---	---	---	72	---
IL 25/STEARNS RD	118+00	123+60	---	---	---	---	---	---	73	123	---	280	---	395	---	---	---	91	---
IL 25/STEARNS RD	124+40	131+00	---	---	---	---	---	---	146	---	---	330	92	1030	---	---	191	55	748
IL 25/STEARNS RD	132+20	146+93.87	---	---	---	---	---	---	437	---	---	850	233	2035	405	---	215	91	3831
STEARNS RD			---	---	---	---	---	---	110	---	---	---	210	785	735	---	221	89	---
GILBERT ST			73	2648	---	53	323	111	73	---	146	---	40	37	---	23	---	129	---
DUNHAM RD RT TURN			---	---	---	---	---	---	---	---	---	---	---	---	373	---	181	---	---
TOTAL			73	4418	20	106	323	158	985	246	175	1910	575	4815	1513	23	808	567	5947

### GUARDRAIL SCHEDULE

LOCATION			63000001	63100070	63100085	63100167	63200310	63301210	63301990	63302700	78200410	48203021
ROAD	STATION	SIDE	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 5 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT (EACH)	GUARDRAIL REMOVAL (FOOT)	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A (FOOT)	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1 (EACH)	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6 (EACH)	GUARDRAIL MARKERS, TYPE A (EACH)	HOT-MIX ASPHALT SHOULDERS, 6" (SQ YD)
IL 25	BREWSTER CREEK	LT	---	---	---	---	---	200.0	1	---	1	78
IL 25	BREWSTER CREEK	RT	---	---	---	---	---	200.0	1	---	2	156
IL 25/STEARNS RD	UPRR	RT	---	---	---	---	210.0	---	---	---	---	---
IL 25/STEARNS RD	E. BRANCH (NW)	LT	37.5	1	---	---	56.25	---	1	---	3	63
IL 25/STEARNS RD	E. BRANCH (NE)	LT	37.5	---	---	---	---	350.0	1	1	3	111
IL 25/STEARNS RD	E. BRANCH (SE)	LT	---	---	1	---	56.25	137.5	1	---	3	81
IL 25/STEARNS RD	E. BRANCH (SW)	RT	137.5	---	1	1	---	---	---	---	3	75
IL 25/STEARNS RD	E. BRANCH (SE)	RT	137.5	---	1	1	---	---	---	---	2	75
TOTAL			350.0	1	3	2	323	887.5	5	1	17	639

### REFLECTIVE PAVEMENT MARKERS

LOCATION			78100100	78100105	78300200
Road	Start STA	End STA	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)
IL 25	102+52.19	106+90.80	---	---	---
IL 25/STEARNS RD	106+90.80	109+17	10	---	10
IL 25/STEARNS RD	110+62	118+00	36	---	36
IL 25/STEARNS RD	118+00	123+60	28	---	28
IL 25/STEARNS RD	124+40	131+00	34	---	34
IL 25/STEARNS RD	132+20	146+93.87	86	6	92
STEARNS RD			---	---	---
GILBERT ST			---	---	---
DUNHAM RD RT TURN			---	---	---
TOTAL			194	6	200