

EXISTING & PROPOSED SIGNING SCHEDULE

STATION	EXISTING OFFSET (LT/RT/CL.)	PROPOSED OFFSET (LT/RT/CL.)	SIGN NO. (MUTCD)	SIZE (INCHES)		AREA (SQ FT)		MESSAGE OR SYMBOL	73700100	72400310	72400710	72400720	72000100	72900100	72900200	72800100	73100100	
						TYPE 1			REMOVE GROUND-MOUNTED SIGN SUPPORT	REMOVE SIGN PANEL, TYPE 1	RELOCATE SIGN PANEL, TYPE 1	RELOCATE SIGN PANEL, TYPE 2	SIGN PANEL, TYPE 1	METAL POSTS, TYPE A	METAL POSTS, TYPE B	TELESCOPING STEEL SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT	
						LESS THAN 9'	9' < X < 24'		EACH	SQ FT	SQ FT	SQ FT	SQ FT	FOOT	FOOT	FOOT	EACH	
GROUND MOUNTED SIGNS				WIDTH	DEPTH													
130+17.94	-	46' LT	W3-3	30	30	6.25												
			D3-1	55	12	4.58				6.25					15 x 2			
130+86.73	45' LT	-	R2-1	24	30	5.00			5.00									
130+86.73	-	45' LT	R2-1	30	36	7.50						7.50	14 x 2					
131+95.40	-	54' RT	SIGN 04	21	24	3.50				3.50			14					
132+21.49	-	56' LT	R3-5	30	36	7.50				7.50			14 x 2					
133+09.89	48' RT	-	R2-1	24	30	5.00			5.00									
133+09.89	-	48' RT	R2-1	30	36	7.50						7.50	14 x 2					
133+84.22	-	12' RT	R3-5	30	36	7.50						7.50			15 x 2		2	
134+77.00	-	56' LT	R3-5	30	36	7.50				7.50			14					
135+38.38	59' LT	-	W1-2(L)	30	30	6.25			6.25									
135+38.38	-	59' LT	W1-2(L)	36	36	9.00						9.00	14 x 2					
136+90.00	-	59' LT	R3-7	36	36	9.00						9.00	14 x 2					
137+42.20	59' LT	-	W10-11	36	36	9.00				9.00								
			M3-1	24	12	2.00												
139+91.58	-	2' RT	M1-1100	24	24	4.00										15 x 2		2
			M5-1	21	15	2.19												
143+28.88	69' LT	-	W9-2	36	36	9.00			9.00									
144+74.62	49' LT	-	R2-1	24	30	5.00			5.00									
144+74.62	-	72' LT	R2-1	30	36	7.50						7.50	14 x 2					
STEARNS RD																		
606+71.46	-	54' LT	W4-3	36	36	9.00						9.00	15 x 2					
606+74.23	-	2' LT	W4-3	36	36	9.00						9.00			15 x 2		2	
608+07.24	-	56' RT	R3-5	30	36	7.50				7.50			14 x 2					
608+12.83	-	4' RT	R3-8	30	30	6.25				6.25								
608+14.59	-	4' RT	R4-7	24	30	5.00				5.00					15		1	
GILBERT ST																		
301+77.34	-	39' RT	SIGN 05	21	27	3.94						3.94						
			SIGN 06	21	27	3.94						3.94			16			
302+73.39	-	-	SIGN 07	21	27	3.94						3.94						
303+95.89	25' LT	-	W14-3	48	36	5.60				5.60				13				
303+95.89	-	25' RT	SIGN 09	60	24		10.00					10.00						
			SIGN 10	60	35		14.58		2			14.58			16 x 2			
304+91.14	-	23' LT	W11-1	30	30	6.25						6.25						
			W16-9P	24	12	2.00						2.00			14			
306+61.95	-	25' RT	SIGN 08	21	27	3.94						3.94			14			
MULTI-USE PATH AT CC&P GRADE CROSSING																		
116+63.86	-	44' LT	W10-1	36	36	9.00						9	14 x 2					
			R15-1	48	9	3.00						6						
117+61.86	-	41' LT	R1-1-3030	30	30	6.25						6.25			15 x 2			
			R15-8	18	9	1.13						1.13						
117+93.66	-	70' LT	W10-1	36	36	9.00						9	14 x 2					
			R15-1	48	9	3.00						6						
119+06.97	-	66' LT	R1-1-3030	30	30	6.25						6.25			15 x 2			
			R15-8	18	9	1.13						1.13						
TOTAL QUANTITY									57	149	205	45	201	751	289	198	13	