

**TEMPORARY EROSION CONTROL SCHEDULE CONT.**

STAGE 2-1				20101000	28001100	28000250	28000305	28000400	28000500	28000510	28100105	X0322916	X0322917	X0322918	X0326694	XX005968	Z0013796
LOCATION				TEMPORARY FENCE	TEMPORARY EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECK	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION	INLET FILTERS	STONE RIPRAP, CLASS A3	PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM SEWER	PLUG EXISTING STORM SEWER	TURBIDITY CURTAIN	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE
Road	Start STA	End STA	SIDE	FOOT	SQ YD	POUND	FOOT	FOOT	EACH	EACH	SQ YD	EACH	EACH	EACH	CU YD	SQ YD	SQYD
IL-25/STEARNS	102+00	110+00	L	-	-	54.72	-	930	-	9	15	-	-	-	-	-	576
IL-25/STEARNS	102+00	110+00	R	-	116.16	55.86	-	-	1	5	24	2	-	-	-	-	-
IL-25/STEARNS	110+00	118+00	L	250	-	0	-	-	-	-	15	5	-	-	-	-	-
IL-25/STEARNS	110+00	118+00	R	-	-	31.92	8	-	2	7	24	1	-	-	-	-	288
<b>TOTAL</b>				<b>250</b>	<b>116</b>	<b>142.50</b>	<b>8</b>	<b>930</b>	<b>3</b>	<b>21</b>	<b>78</b>	<b>8</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>864</b>
STAGE 2				20101000	28001100	28000250	28000305	28000400	28000500	28000510	28100105	X0322916	X0322917	X0322918	X0326694	XX005968	Z0013796
LOCATION				TEMPORARY FENCE	TEMPORARY EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECK	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION	INLET FILTERS	STONE RIPRAP, CLASS A3	PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM SEWER	PLUG EXISTING STORM SEWER	TURBIDITY CURTAIN	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE
Road	Start STA	End STA	SIDE	FOOT	SQ YD	POUND	FOOT	FOOT	EACH	EACH	SQ YD	EACH	EACH	EACH	CU YD	SQ YD	SQYD
IL-25/STEARNS	117+00	123+21.69	L	-	525.1	11.40	-	-	-	-	-	3	2	-	-	-	-
IL-25/STEARNS	117+00	123+21.69	R	-	778.3	55.86	8	-	-	11	-	1	-	-	-	-	-
IL-25/STEARNS	123+21.69	131+21.68	L	-	-	0.00	-	-	-	1	-	1	4	-	-	-	-
IL-25/STEARNS	123+21.69	131+21.68	R	-	197.5	75.24	72	711.0	1	7	-	1	-	-	-	-	288
EXUPRR	20008+49.91	20012+00.00	L	-	-	0.00	-	-	-	-	-	-	-	-	-	-	-
EXUPRR	2008+49.91	20012+00	R	-	-	0.00	-	-	-	-	-	-	-	-	-	-	-
<b>TOTAL</b>				<b>0</b>	<b>1,501</b>	<b>142.50</b>	<b>80</b>	<b>711</b>	<b>1</b>	<b>19</b>	<b>0</b>	<b>6</b>	<b>6</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>288</b>
STAGE 3				20101000	28001100	28000250	28000305	28000400	28000500	28000510	28100105	X0322916	X0322917	X0322918	X0326694	XX005968	Z0013796
LOCATION				TEMPORARY FENCE	TEMPORARY EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECK	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION	INLET FILTERS	STONE RIPRAP, CLASS A3	PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM SEWER	PLUG EXISTING STORM SEWER	TURBIDITY CURTAIN	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE
Road	Start STA	End STA	SIDE	FOOT	SQ YD	POUND	FOOT	FOOT	EACH	EACH	SQ YD	EACH	EACH	EACH	CU YD	SQ YD	SQYD
IL-25/STEARNS	110+00	118+00	M	-	-	46.74	32	-	-	-	-	-	-	-	-	-	-
IL-25/STEARNS	118+00	124+00	L	459	-	28.50	-	-	-	4	-	-	-	4	-	-	-
IL-25/STEARNS	118+00	124+00	M	-	-	25.08	16	-	-	-	-	-	-	-	-	-	-
IL-25/STEARNS	124+00	130+00	M	-	-	21.66	40	-	-	-	-	-	-	-	-	-	-
IL-25/STEARNS	130+00	142+40	L	-	-	27.36	-	-	-	-	-	2	-	-	-	-	-
IL-25/STEARNS	130+00	142+40	R	-	-	0.00	-	-	1	3	-	-	-	-	-	-	-
IL-25/STEARNS	130+00	142+40	M	-	-	0.00	24	-	-	1	-	-	-	-	-	-	-
BREWSTER CREEK				-	-	0.00	-	-	-	-	-	-	-	-	-	-	-
<b>TOTAL</b>				<b>459</b>	<b>0</b>	<b>149.34</b>	<b>112</b>	<b>0</b>	<b>1</b>	<b>8</b>	<b>0</b>	<b>2</b>	<b>0</b>	<b>4</b>	<b>0</b>	<b>0</b>	<b>0</b>
<b>TOTAL</b>				<b>2498</b>	<b>14,398</b>	<b>1,056</b>	<b>578</b>	<b>7,667</b>	<b>9</b>	<b>113</b>	<b>108</b>	<b>22</b>	<b>24</b>	<b>7</b>	<b>0.30</b>	<b>100</b>	<b>4,896</b>

FILE NAME: \\D163598-shl-t-schedule-66.dgn	DESIGNED - AAF	REVISED -
USER NAME: tolok	DRAWN - TMB	REVISED -
PLOT DATE: 1/17/2013	CHECKED - JMM	REVISED -
	DATE - 01/18/2013	REVISED -



**STATE OF ILLINOIS**  
**DIVISION OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: NTS SHEET NO. 6 OF 8 SHEETS STA. TO STA.

F.A.S. RTE. 361	SECTION 06-00214-18-RP	COUNTY KANE	TOTAL SHEETS 451	SHEET NO. 40
CONTRACT NO. 63598			ILLINOIS FED. AID PROJECT	