

LANDSCAPING SCHEDULE

LOCATION			25000210	25000400	25000700	XX006701	XX006709
			SEEDING CLASS 2A	NITROGEN FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	SEEDING, CLASS 4 (MODIFIED) MESIC PRAIRIE	SEEDING, CLASS 5 (MODIFIED) MESIC PRAIRIE
ROAD	STATION TO	STATION FROM	ACRE	POUND	TON	ACRE	ACRE
IL-25/STEARNS	102+52.19	110+00.00	1.00	90	2	0.07	0.07
IL-25/STEARNS	110+00.00	118+00.00	1.15	104	2.3	0.03	0.03
IL-25/STEARNS	118+00.00	123+00.00	1.00	90	2	0.24	0.24
IL-25/STEARNS	123+61.95	131+50.00	0.74	67	1.48	1.04	1.04
IL-25/STEARNS	131+50.00	138+55.00	0.43	39	0.86	0.17	0.17
IL-25/STEARNS	138+55.00	147+82.18	0.86	77	1.72	0.27	0.27
UPRR SF	1994+96.37	2000+10.37		0		0.30	0.30
UPRR SF	2002+00.00	2005+84.24		0		0.30	0.30
GILBERT			0.37	33	0.74		
TOTALS			5.75	518	11.5	2.50	2.50

DRAINAGE REMOVAL SCHEDULE

LOCATION			50106220	60500040	60500050	X0322054	X5510100
			PIPE CULVERT REMOVAL	REMOVING MANHOLE S	REMOVING CATCH BASINS	REMOVAL OF PRECAST FLARED END SECTION	STORM SEWER REMOVAL
ROAD	Station From	Station To	(FT)	(EACH)	(EACH)	(EACH)	(FT)
IL-25/STEARNS	102+52.58	108+98.50			2		
IL-25/STEARNS	108+98.50	111+72.64					
IL-25/STEARNS	111+71.64	117+95.62			1	1	102
IL-25/STEARNS	118+28.23	123+12.37		3		2	635
IL-25/STEARNS	124+63.68	130+41.65	126			2	126
IL-25/STEARNS	130+41.65	132+40.38					
IL-25/STEARNS	132+40.38	138+03.06					
IL-25/STEARNS	139+12.85	146+95.06			9		391
GILBERT ST				2	2	1	229
NORTH STEARNS				1	1		
TOTALS			126	6	15	6	1484

REMOVAL SCHEDULE

LOCATION			20100110	20100210	44000200	44000500	44004250	44003100	Z0029999	Z0022800	X0326401	X0327036
			TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	PAVED SHOULDER REMOVAL	MEDIAN REMOVAL	IMPACT ATTENUATOR REMOVAL	FENCE REMOVAL	BARRIER WALL REMOVAL	BIKE PATH REMOVAL
ROAD	Station From	Station To	UNIT	UNIT	(SQ YD)	(FOOT)	(SQ YD)	(1085)	EACH	(12)	(FT)	(SQ YD)
IL-25/STEARNS	102+52.58	108+98.50	68	183	216		683	126		35		
IL-25/STEARNS	108+98.50	111+72.64					89					
IL-25/STEARNS	111+71.64	117+95.62			97		534	303		9		
IL-25/STEARNS	118+28.23	123+12.37			189	30	880		2	14	115	540
IL-25/STEARNS	124+63.68	130+41.65				140	451			6		646
IL-25/STEARNS	130+41.65	132+40.38			988		25					171
IL-25/STEARNS	132+40.38	138+03.06					720					287
IL-25/STEARNS	139+12.85	146+95.06				881	360					
GILBERT ST					517	539	289			117		40
NORTH STEARNS						171	137	1303		56		
TEMP PAVEMENT												
TEMP PAV (VAR D)										210		
TOTALS			68	183	2007	1761	4167	452	2	447	115	1685

FILE NAME =	DESIGNED - AAF	REVISED -
...X032598-shd-sched.dwg	DRAWN - TMB	REVISED -
USER NAME = dbench	CHECKED - JMM	REVISED -
PLOT DATE = 1/17/2013	DATE - 01/18/2013	REVISED -



**STATE OF ILLINOIS
DIVISION OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NTS	SHEET NO. 8 OF 8 SHEETS	STA. TO STA.	F.A.P. RTE. 361	SECTION 06-00214-1B-RP	COUNTY KANE	TOTAL SHEETS 45	SHEET NO. 42
						CONTRACT NO. 63598	
ILLINOIS FED. AID PROJECT							