

NO.	AREAS CHECKED	DATE
FINAL SURVEY		
NOTE BOOK		
SURVEYED		
PICTURED		
TEMPERATURE		
AREAS CHECKED		

- | | | | |
|-----------|---------------|----|------|
| ORIGINAL | SURVEYED | BY | DATE |
| NOTE BOOK | PLOTTED | | |
| AREAS | TEMPERATURE | | |
| NO. | AREAS CHECKED | | |

63. WHEN THE PCC SIDEWALK EXTENDS THROUGH THE DRIVEWAY, THE THICKNESS OF THE SIDEWALK IN THE DRIVEWAY AREA SHALL BE THE SAME AS THE DRIVEWAY THICKNESS (BUT NOT LESS THAN 5"). SIDEWALK WILL BE PAID FOR AS PCC SIDEWALK 5" REGARDLESS OF THE THICKNESS. SIDEWALK CROSS SLOPE THRU DRIVEWAY AREA TO BE A MAXIMUM OF 1:50.

- ### PAVEMENT MARKING

- ## SIGNING, STRIPING & LANDSCAPING

73. TWO MOBILIZATIONS FOR LANDSCAPING WILL BE REQUIRED FOR THIS PROJECT TO PLACE PERMANENT LANDSCAPING ON NORTH SIDE OF WASHINGTON STREET IN STAGE OF CONSTRUCTION 1 AND SOUTH SIDE IN STAGE OF CONSTRUCTION 2. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR THE ADDITIONAL MOBILIZATIONS.

- | BENCHMARK TABLE | | | |
|-----------------|------------------------|---|-----------|
| NUMBER | 1STA & OFFSET | DESCRIPTION | ELEVATION |
| B.M. #1-42AR | 62+79.11
34.15' RT | FOUND CROSS CUT IN SOUTHEAST CORNER OF TRAFFIC SIGNAL HANDHOLE IN THE SOUTHWEST QUADRANT OF THE INTERSECTION OF WASHINGTON STREET AND HAINESVILLE ROAD. | 802.84 |
| REFERENCE B.M. | 63+34.34
37.80' RT | FOUND BENCHMARK SPIKE IN POWER POLE IN THE SOUTHEAST QUADRANT OF THE INTERSECTION OF WASHINGTON STREET AND HAINESVILLE ROAD. | 804.28 |
| T.B.M. #1 | 200+58.02
65.60' RT | FOUND CROSS CUT IN NORTHERLY FLANGE BOLT OF FIRE HYDRANT IN THE SOUTH QUADRANT OF THE INTERSECTION OF CEDAR LAKE ROAD AND WASHINGTON STREET. | 764.96 |
| T.B.M. #2 | 20+32.93
27.67' LT | RAILROAD SPIKE SET IN POWER POLE ON THE NORTH SIDE OF WASHINGTON STREET 4' WEST OF THE CENTERLINE OF BEECHWOOD DRIVE EXTENDED. | 785.20 |
| T.B.M. #3 | 34+10.10
28.57' LT | RAILROAD SPIKE SET IN POWER POLE ON THE NORTH SIDE OF WASHINGTON STREET 153' EAST OF THE EAST R.O.W. LINE OF CLIFTON DRIVE. | 793.77 |
| T.B.M. #4 | 47+28.63
31.18' RT | RAILROAD SPIKE SET IN POWER POLE ON THE SOUTH SIDE OF WASHINGTON STREET 120' EAST OF THE EAST R.O.W. LINE OF PROSPECT DRIVE. | 811.36 |

- ## POINTS OF CONTACT

LAKE COUNTY PUBLIC WORKS
MR. GORDON WHITE, P.E.
PRINCIPAL CIVIL ENGINEER
650 WINCHESTER RD.
LIBERTYVILLE, IL 60048
PH: 847.377.7500
FX: 847.377.7173
gwhite2@lakecountyil.gov

NICOR GAS
MS. CONSTANCE LANE
UTILITY CONSULTANT
P.O. BOX 190
AURORA, IL 60507-0190
PH: 630.388.3830
FX: 630.983.4028
clone@nicor.com

COMCAST
MR. ROBERT SCHULTER
MANAGER
688 INDUSTRIAL DR
ELMHURST, IL 60126
PH: 630.600.6347
FX: 630.600.6390
bob.schulter@comcast.com

PAGE
MR. ALLAN LEE
SECTION MANAGER
PASSENGER AMENITIES
PH: 708.649.3231
FX: 708.649.3251
allan.lee@pacebus.com

VILLAGE OF ROUND LAKE PARK
PUBLIC WORKS DEPARTMENT
MR. GEORGE JOHNSON
SUPERINTENDENT
37 PORTER DRIVE
ROUND LAKE PARK, IL 60073
PH: 847.812.9171
mjnelson@roundlakepark.us

 450 E Devon Ave, Suite 300 Itasca, Illinois 60143 Tel: 630.773.3900 Fax: 630.773.3975 www.civiltechinc.com	DESIGNED - PK	REVISED - 4/10/2013	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - JRR	REVISED -			0187	05-00121-07-WR	LAKE	223	3
	CHECKED - RTM	REVISED -			CONTRACT NO. 63765				
	DATE - 12/17/2012	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
					SHEET NO. 2 OF 2 SHEETS				