

142

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN TOTAL QUANTITY	STATE	COAL VALLEY	ROCK ISLAND
				0011 80% FED/ 20% STATE	0028 100%	0005 100%
30300124	AGGREGATE SUBGRADE IMPROVEMENT 24"	SQ YD	1,128	1,128		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1,105	773	332	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	11		6
40600300	AGGREGATE (PRIME COAT)	TON	63	16		47
40600525	LEVELING BINDER (HAND METHOD), N50	TON	15			15
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	5,533	5,533		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	394	394		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	89			89
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2,552	1,265		1,287
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	557	557		
40603415	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, N50	TON	116		116	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	101	101		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	1,043	1,043		
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7"	SQ YD	825	825		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	837.5	837.5		
42400800	DETECTABLE WARNINGS	SQ FT	45		45	
44000100	PAVEMENT REMOVAL	SQ YD	2,542	2,542		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	13,379			13,379
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	335	335		
44000400	GUTTER REMOVAL	FOOT	55	55		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	61	31		30
44004000	PAVED DITCH REMOVAL	FOOT	273	273		
44004250	PAVED SHOULDER REMOVAL	SQ YD	6,306	6,306		
44213200	SAW CUTS	FOOT	5,003.70	5,003.70		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	271	271		

\*SPECIALTY ITEMS

Rev.