

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	STATE	COAL VALLEY	ROCK ISLAND
				0011	0028	0005
			<i>URBAN</i>	80% FED/ 20% STATE	100%	100%
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	5,725	5,725		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	788	788		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2		
50105220	PIPE CULVERT REMOVAL	FOOT	334	334		
50200100	STRUCTURE EXCAVATION	CU YD	118	118		
50300225	CONCRETE STRUCTURES	CU YD	107.0	107.0		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	<i>489</i>	<i>489</i>		
50300260	BRIDGE DECK GROOVING	SQ YD	1,011	1,011		
50300280	CONCRETE ENCASEMENT	CU YD	7.60	7.60		
50300300	PROTECTIVE COAT	SQ YD	1,395	1,395		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1		
50500505	STUD SHEAR CONNECTORS	EACH	4,312	4,312		
50800105	REINFORCEMENT BARS	POUND	68.36	68.36		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	<i>125,150</i>	<i>125,150</i>		
50800515	BAR SPLICERS	EACH	724	724		
50901720	BICYCLE RAILING	FOOT	152.00	152.00		
50901750	PARAPET RAILING	FOOT	<i>149</i>	<i>149</i>		
51201400	FURNISHING STEEL PILES HP10X42	FOOT	483	483		
51202305	DRIVING PILES	FOOT	483	483		
51203400	TEST PILE STEEL HP10X42	EACH	1	1		
51500100	NAME PLATES	EACH	1	1		
52100520	ANCHOR BOLTS, 1"	EACH	44	44		
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 01	EACH	2	2		
54002020	EXPANSION BOLTS 3/4 INCH	EACH	12	12		

\*SPECIALTY ITEMS

FILE NAME *	USER NAME * rnkrsru	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
Default	cs:\p-work\p\idotr\ankrsru\dos3669110205564-sht-schedules.dgn	DRAWN -	REVISED -			5786	40BR	Rock Island	225	5	
	PLOT SCALE * 100.0000 ' / in.	CHECKED -	REVISED -			SCALE: SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			
	PLOT DATE * Fri Feb 01 15:26:18 2013	DATE -	REVISED -			CONTRACT NO. 64341					

*Rev.*