

SCHEDULE OF QUANTITIES

44000500 COMBINATION CURB AND GUTTER REMOVAL

FOOT	LOCATION	
	Niabi Zoo Rd Reconstruction	
31	LT	19+49.81 - 19+81.00
	Resurfacing	
5	LT	12+00.00
5	LT	16+00.00
5	LT	19+00.00
5	LT	22+00.00
5	LT	25+00.00
5	LT	28+00.00
<u>61</u>		

44004000 PAVED DITCH REMOVAL

FOOT	LOCATION		NOTE
	Niabi Zoo Rd		
273	LT	16+36.53 - 19+09.07	12' WIDE
<u>273</u>			

50104400 CONCRETE HEADWALL REMOVAL

EACH	LOCATION		NOTE
	US Rte 6		
2	LT & RT	387+55.32	5' X 5' BOX CULVERT
<u>2</u>			

50105220 PIPE CULVERT REMOVAL

FOOT	LOCATION		OFFSET	NOTE
	US Rte 6			
42	RT	376+29.35	44.51'	15" W/END SECTIONS
60	RT	388+16.20	43.71'	30" W/END SECTIONS
	Niabi Zoo Rd			
78	RT	11+59.36	29.45' - 108.16'	
108	LT	15+90.72	16.30' - 70.48'	2 - 30" W/END SECTIONS
46	RT	16+08.85	80.33'	18" W/END SECTION
<u>334</u>				

54001001 BOX CULVERT END SECTIONS, CULVERT NO. 01

EACH	LOCATION		OFFSET
	US Rte 6		
1	LT	387+55.32	41'
1	RT	387+55.32	45'
<u>2</u>			

54002020 EXPANSION BOLTS 3/4 INCH

EACH	LOCATION	
	US Rte 6	
12	LT & RT	3875+55.32
<u>12</u>		

54010505 PRECAST CONCRETE BOX CULVERTS 5' X 5'

FOOT	LOCATION	
	US Rte 6	
10.00	LT	387+55.32
15.00	RT	387+55.32
<u>25.00</u>		

54215550 METAL END SECTION 15'

EACH	LOCATION		OFFSET
	US Rte 6		
1	RT	376+04.56	48'
1	RT	376+54.55	51'
	Niabi Zoo Rd		
1	RT	19+05.52	33'
<u>3</u>			

54215553 METAL END SECTION 18'

EACH	LOCATION		OFFSET	NOTE
	Niabi Zoo Rd			
1	LT	16+44.16	49.54'	78th Avenue
<u>1</u>				

54215565 METAL END SECTION 30'

EACH	LOCATION		OFFSET
	Niabi Zoo Rd		
1	LT	16+03.81	36.14'
1	LT	16+35.79	33.82'
<u>2</u>			

54215571 METAL END SECTION 36'

EACH	LOCATION		OFFSET
	US Rte 6		
1	RT	381+28.70	88'
<u>1</u>			

54244405 FLUSH INLET BOX FOR MEDIAN, STANDARD 542546

EACH	LOCATION	
	NIABI ZOO RD	
1	RT	16+56.96
1	RT	17+66.43
<u>2</u>		

54248510 CONCRETE COLLAR

CU YD	LOCATION	
	US Rte 6	
1.34	LT & RT	387+55.32
<u>1.34</u>		

54260311 TRANSVERSABLE PIPE GRATE

FOOT	LOCATION		OFFSET	NOTE
	US Rte 6			
33.50	LT	387+55.32	41'	5' X 5' BOX CUL. END SEC. - 2@4'-8" AND 1@24'-2"
33.50	RT	387+55.32	45'	5' X 5' BOX CUL. END SEC. - 2@4'-8" AND 1@24'-2"
	Niabi Zoo Rd			
18.33	LT	15+87.66	21'	30" PIP CUL. END SEC. - 1@3'-6" AND 1@14'-10"
18.33	LT	15+84.85	21'	30" PIP CUL. END SEC. - 1@3'-6" AND 1@14'-10"
<u>103.66</u>				

54261436 CONCRETE END SECTION, STANDARD 542001, 30", 1:4

EACH	LOCATION		OFFSET
	Niabi Zoo Rd		
1	LT	10+80.16	68.68'
<u>1</u>			