

SCHEDULE OF QUANTITIES

60260100	INLETS TO BE ADJUSTED		
EACH	LOCATION		
	Niabi Zoo Rd Resurfacing		
1	LT	12+00.00	
1	LT	16+00.00	
1	LT	19+00.00	
1	LT	22+00.00	
1	LT	25+00.00	
1	LT	28+00.00	
<u>6</u>			

60600095	CLASS SI CONCRETE (OUTLET)		
CU YD	LOCATION		
	Niabi Zoo Rd		
1.11	LT	18+00.00 - 18+60.13	
<u>1.1</u>			

60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24		
FOOT	LOCATION		
	Niabi Zoo Rd		
121	LT	18+60.13 - 19+81.00	
<u>121</u>			

60608552	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06			OFFSET
FOOT	LOCATION			
	US Rte 6			
61	RT	385+08.39 - 385+26.68	27' - 43'	
<u>61</u>				

60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24		
FOOT	LOCATION		
	Niabi Zoo Road Resurfacing		
5	LT	12+00.00	
5	LT	16+00.00	
5	LT	19+00.00	
5	LT	22+00.00	
5	LT	25+00.00	
5	LT	28+00.00	
<u>30</u>			

60618300	CONCRETE MEDIAN SURFACE, 4 INCH			OFFSET
SQ FT	LOCATION			
	US Rte 6			
111	RT	385+08.39 - 385+26.68	27' - 43'	
<u>111</u>				

60801036	FLAP GATE 36"			OFFSET
EACH	LOCATION			
	US Rte 6			
1	RT	383+00.04	62'	
	Niabi Zoo Rd			
1	RT	10+80.32	145'	
<u>2</u>				

63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS		
FOOT	LOCATION		
	US Rte 6		
25.0	LT	384+44.15 - 384+69.15	
<u>25.0</u>			

63100085	TRAFFIC BARRIER TERMINAL, TYPE 6		
EACH	LOCATION		
	US Rte 6		
1	LT	383+98.50 - 384+44.15	
<u>1</u>			

63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (FLARED)		
EACH	LOCATION		
	US Rte 6		
1	LT	384+69.15 - 385+19.51	
<u>1</u>			

63200310	GUARDRAIL REMOVAL		
FOOT	LOCATION		
	US Rte 6		
94	LT	382+22.28 - 383+15.78	
61	RT	382+55.00 - 383+15.75	
135	LT	383+65.23 - 385+00.01	
	Niabi Zoo Rd		
152	RT	10+22.93 - 11+75.01	
<u>441</u>			

63500105	DELINEATORS			NOTE
EACH	LOCATION			
	US Rte 6			
2	LT & RT	374+25.00		
2	LT & RT	378+64.38		
1	LT	385+19.51		GUARDRAIL
2	LT & RT	388+15.38		
2	LT & RT	392+15.38		
	Niabi Zoo Rd			
2	LT & RT	10+80.32		PIPE CULVERT
2	LT & RT	10+95.00		
2	LT & RT	12+95.00		
2	LT & RT	14+35.00		
2	LT & RT	15+05.00		
2	LT & RT	15+75.00		
1	RT	16+27.63		
1	LT	16+37.17		PIPE CULVERT
2	LT & RT	16+75.00		
2	LT & RT	17+80.00		
2	LT & RT	18+50.00		
2	LT & RT	19+50.00		
<u>31</u>				

66500105	WOVEN WIRE FENCE, 4'		
FOOT	LOCATION		
	US Rte 6		
701	LT	375+66.00 - 382+67.00	
1,200	LT	384+00.00 - 396+00.00	
<u>701</u>			